

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 017 COMANCHE SW 1/4 NE 1/4 NE 1/4 20 T 32 S R 18 W

Distance and direction from nearest town or city street address of well if located within city?
 2 E. 2 S. OF COLDWATER, KS

2 WATER WELL OWNER: ABERCROMBIE RTD INC 372
 RR#, St. Address, Box #: 150 N. MAIN SUITE 801 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: WICHITA, KS 67202- Application Number:

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

/ \				
1	NW		NE	X
M				
i	W			E
l				
e		SW		SE
\ /				

4 DEPTH OF COMPLETED WELL 220 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 90 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 90 ft. below land surface measured on mo/day/yr
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 8.75 in. to 220 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 06 OIL FIELD

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 200 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 26-21
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 200 ft. to 220 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 220 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 15 OIL/GAS WELL
 Direction from well? SW How many feet? 60

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	49	TAN CLAY			
49	55	WHITE CLAY			
55	95	TAN CLAY			
95	114	05 SAND AND 17 GRAVEL			
114	196	TAN CLAY			
196	218	05 SAND AND 17 GRAVEL			
218	220	TAN CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
 completed on (mo/day/year) 10/23/96 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 11/12/96
 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse