


USE TYPEWRITER OR BALL
POINT PEN. PRESS FIRMLY.
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County <u>Comanche</u>		Fraction <u>SW 1/4 SW 1/4 NW 1/4</u>	Section number <u>17</u>	Township number <u>T 32 S</u>	Range number <u>R 18 W</u>
2. Distance and direction from nearest town or city: <u>1 mile East & 1/2 mile South of Coldwater, Ks</u>		3. Owner of well: <u>Comanche County RWD No. 2</u> R.R. or street: <u>Coldwater, Kansas</u> City, state, zip code: <u>67029</u>			
4. Locate with "X" in section below: Sketch map: <u>Well No. 1 (TH 1-76)</u>		6. Bore hole dia. <u>30</u> in. Completion date <u>2-25-77</u> Well depth <u>205</u> ft.			
		7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary			
		8. Use: Domestic ☒ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other ☐			
5. Type and color of material		From	To	9. Casing: Material <u>Stl.</u> Height: Above or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>43.77</u> lbs./ft. Dia. <u>12</u> in. to <u>182</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>330</u>	
Top soil		0	2	10. Screen: Manufacturer's name <u>Cook</u> Type <u>Steel</u> Dia. <u>12"</u> Slot/gauze <u> </u> Length <u>24'</u> Set between <u>176</u> ft. and <u>182</u> ft. <u>187</u> ft. and <u>205</u> ft. Gravel pack? <u>yes</u> Size range of material <u>1/4 x 1/2</u>	
Clay		2	12	11. Static water level: <u>81.90</u> ft. below land surface Date <u>2/24/77</u> mo./day/yr.	
Fine sand & clay		12	17	12. Pumping level below land surfaces: <u>119</u> ft. after <u>4</u> hrs. pumping <u>300</u> g.p.m. ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>600</u> g.p.m.	
Clay		17	42	13. Water sample submitted: <u> </u> mo./day/yr. Yes ☒ No ☐ Date <u> </u>	
Med. to co. sand & med. gravel		42	90	14. Well head completion: ☒ Pitless adapter <u> </u> inches above grade	
Clay		90	96	15. Well grouted? <u>Yes</u> With: <u> </u> Neat cement <u> </u> Bentonite ☒ Concrete <u> </u> Depth: From <u>5</u> ft. to <u>20</u> ft.	
Fine to co. sand & med. gravel		96	110	16. Nearest source of possible contamination: ft. <u>1400</u> Direction <u>West</u> Type <u>Farm</u> Well disinfected upon completion? ☒ Yes ☐ No	
Clay		110	116	17. Pump: <u> </u> Not installed Manufacturer's name <u>Hydropower, Inc.</u> Model number <u>756-828</u> HP <u>7 1/2</u> Volts <u>230</u> Length of drop pipe <u>147</u> ft. capacity <u>70</u> g.p.m. Type: ☒ Submersible <u> </u> Turbine <u> </u> <u> </u> Jet <u> </u> Reciprocating <u> </u> <u> </u> Centrifugal <u> </u> Other <u> </u>	
Clay		116	128		
Fine to co. sand & gravel		128	160		
Clay		160	184		
Med. to co. sand & gravel		184	188		
Clay		188	205		
Clay		205	215		
(Use a second sheet if needed)					
18. Elevation: Topography: <u> </u> Hill <u> </u> Slope ☒ Upland <u> </u> Valley		19. Remarks: <u>Well location is 100' N. & 100' E. of SW corner of NW 1/4 of Section 17, T32S, R18W Comanche Co., Kansas</u>		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Layne Western Co.</u> 102 Business name <u>Wichita, Kansas</u> License No. <u> </u> Address <u> </u> Signed <u> </u> Date <u>3-8-77</u> Authorized representative	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5