


T		R		EW		sec	1/4	1/4	1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

County COMANCHE	Township name PROTECTION	Fraction SE SW - SE NE SW - SE	Section number 7	Town number 32 S	Range number 20 W																														
1 Location of well: Distance and direction from nearest town or city: N-4 MILES Street address of well location if in city: W-2 1/2 "			3 Owner of well: JR. SUBANK Address: PROTECTION, KAN. 67127																																
Locate with "X" in section below: 			Sketch map:																																
2 Type and color of material <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 60%;">Type and color of material</th> <th style="width: 10%;">From</th> <th style="width: 10%;">To</th> </tr> </thead> <tbody> <tr> <td>SANDY TOP SOIL</td> <td>0</td> <td>3</td> </tr> <tr> <td>CLAY, TAN-TO BROWN</td> <td>3</td> <td>24</td> </tr> <tr> <td>CLAY, VERY DARK, NEAR BLACK</td> <td>24</td> <td>40</td> </tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table> (One of the few wells in this area to produce from clay) (use a second sheet if needed)			Type and color of material	From	To	SANDY TOP SOIL	0	3	CLAY, TAN-TO BROWN	3	24	CLAY, VERY DARK, NEAR BLACK	24	40																			4 Well depth: 40 ft. Date of completion 12-3-74 Well diameter 8 in. 5 ☒ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary 6 Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well ☒ PASTURE 7 Casing: Material STYRENE Weight: above/below Threaded ☐ Welded ☐ Surface 16 in. Dig. Weight 1 1/2 lbs./ft. 5 in. to 40 ft. depth Drive shoe? ☐ Yes ☒ No in. to ft. depth 8 Screen: Manufacturer JESS + LOWEL Type STYRENE Dia. 3 Slot/gauze SAWCUT Length 15' Set between 25 ft. and 40 ft. Fittings: Gravel pack ☒ Yes ☐ No Size range of material 3/4" 9 Static water level: 15 ft. below land surface Date 12-3-74 10 Pumping level below land surfaces: ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield 8 g.p.m. 11 Water sample submitted: ☐ Yes ☒ No Date _____ 12 Well head completion: ☐ Pitless adapter 16 inches above grade 13 Well grouted? ☒ Yes ☐ No ☐ Neat cement ☐ Bentonite ☒ CONCRETE Depth: From 0 ft. to 10 ft. 14 Nearest source of possible contamination: ft. NONE Direction OPEN WHEAT FIELD Type _____ Well disinfected upon completion? ☒ Yes ☐ No 15 Pump: Not installed Manufacturer's name ARMITER Model number _____ HP WIND Volts _____ Length of drop pipe 26 ft. capacity _____ g.m.p. Type: ☐ Submersible ☐ Turbine ☐ Jet ☒ Reciprocating ☐ Centrifugal ☐ Other 16 Remarks: elevation 37 inches of 6 5/8 iron pipe set in concrete to protect styrene 16" above ground Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley 17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. WYMER BLACKSMITH SHOP 228 Business name License No. _____ Address PROTECTION, KANS. Signed Kenneth Wymer Date 12-7-74 Authorized representative		
			Type and color of material	From	To																														
			SANDY TOP SOIL	0	3																														
			CLAY, TAN-TO BROWN	3	24																														
			CLAY, VERY DARK, NEAR BLACK	24	40																														