

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 060 MEADE : *NO N/C SE 1/4* : 11 : T 32 S : R 28 W

Distance and direction from nearest town or city street address of well if located within city?
 1/4 MILE SOUTH AND 1/4 MILE EAST OF MEADE

2 WATER WELL OWNER: HOOVER, DORTHY
 RR#, St. Address, Box # : 218 N PERSHING Board of Agriculture, Division of Water Resources
 City, State, ZIP code : LIBERAL, KS 67901- Application Number: 3882

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 168 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \				WELL'S STATIC WATER LEVEL 25 ft. below land surface measured on mo/day/yr 05/10/94			
				Pump testdata: Well water was 70 ft. after 1 hours pumping 693 gpm			
1	NW		NE	Estimated Yield 600 gpm: Well water was ' ft. after 0 hours pumping 0 gpm			
M				Bore Hole Diameter 24 in. to 168 ft., and in. to 0 ft.			
W			E	WELL WATER TO BE USED AS: 02 IRRIGATION			
	SW		SE	Was a chemical/bacteriological sample submitted to department? No ;			
\ /				If yes, mo/day/yr sample was submitted Water well disinfected? Yes			

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 16 in. to 168 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 16 lbs/ft. Wall thickness or gauge No. .50
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 68 ft. to 168 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 168 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTHEAST How many feet? 71

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	10	01 CLAY 31 CALICHE			
10	14	07 FINE SAND 08 MEDIUM SAND 28 ROCK			
14	18	04 SANDY CLAY			
18	23	01 CLAY			
23	27	05 SAND 28 ROCK 04 SANDY CLAY			
27	36	01 CLAY 04 SANDY CLAY 05 SAND			
36	47	07 FINE SAND 08 MEDIUM SAND 15 CRS GRAVEL			
47	59	01 CLAY 04 SANDY CLAY			
59	72	05 SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/09/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/16/94 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 060 MEADE	SE 1/4 1/4 1/4	11	T 32 S	R 28 W

2 WATER WELL OWNER:	HOOVER DORTHY	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	218 N PERSHING	Application Number: 3882
City, State, ZIP code :	LIBERAL, KS 67901-	

FROM	TO	LITHOLOGIC LOG
72	74	01 CLAY
74	87	08 MEDIUM SAND 09 COARSE SAND
87	99	01 CLAY 04 SANDY CLAY
99	111	20 LIMESTONE 05 SAND 04 SANDY CLAY
111	125	05 SAND 20 LIMESTONE 28 ROCK
125	129	04 SANDY CLAY 05 SAND
129	139	07 FINE SAND 08 MEDIUM SAND 11 GRAVEL
139	146	04 SANDY CLAY
146	152	04 SANDY CLAY 20 LIMESTONE
152	157	04 SANDY CLAY 20 LIMESTONE
157	165	07 FINE SAND 08 MEDIUM SAND 04 SANDY CLAY
165	173	04 SANDY CLAY 05 SAND 20 LIMESTONE
173	195	01 CLAY
195	198	04 SANDY CLAY
198	207	01 CLAY 36 GYP ROCK
207	260	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/09/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/16/94 under the business name of HENKLE DRILLING & SUPPLY by (signature) 