

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 060 MEADE NW 1/4 NE 1/4 NW 1/4 6 T 32 S R 28 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 3 3/4 MILES WEST, & 1/2 MILE NORTH OF MEADE

2 WATER WELL OWNER: CLAWSON, MARY
 RR#, St. Address, Box #: RR 1, BOX 65F Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SATANTA, KS 67870- Application Number: 6,811

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 525 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 170 ft. below land surface measured on mo/day/yr 04/11/95 Pump testdata: Well water was 210 ft. after 4 hours pumping 1740 gpm
Estimated Yield 1740 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 24 in. to 525 ft., and in. to 0 ft.
WELL WATER TO BE USED AS: 02 IRRIGATION
Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 525 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .25
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 215 ft. to 245 ft., From 410 ft. to 450 ft.
 From 283 ft. to 383 ft., From 505 ft. to 525 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 525 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout intervals: From 0 ft. to 0 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? WEST How many feet? 280

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	8	04 SANDY CLAY			
8	20	01 CLAY 04 SANDY CLAY 31 CALICHE			
20	28	01 CLAY 31 CALICHE			
28	42	01 CLAY 31 CALICHE			
42	59	01 CLAY			
59	72	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
72	77	01 CLAY			
77	90	04 SANDY CLAY			
90	128	05 SAND 13 FINE GRAVEL 15 CRS GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/07/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/21/95 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
COUNTY: 060 MEADE : NW 1/4 NE 1/4 NW 1/4 : 6 : T 32 S : R 28 W

2 WATER WELL OWNER: CLAWSON, MARY
RR#, St. Address, Box #: RR 1, BOX 65F Board of Agriculture, Division of Water Resources
City, State, ZIP code : SATANTA, KS 67870- Application Number: 6,811

FROM	TO	LITHOLOGIC LOG
128	135	04 SANDY CLAY 05 SAND
135	141	01 CLAY 04 SANDY CLAY
141	166	04 SANDY CLAY
166	241	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
241	264	19 SHALE 01 CLAY
264	280	01 CLAY 05 SAND
280	290	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
290	365	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
365	373	05 SAND 04 SANDY CLAY 01 CLAY
373	383	29 ROCK & SAND 04 SANDY CLAY 31 CALICHE
383	410	04 SANDY CLAY 07 FINE SAND
410	418	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
418	448	07 FINE SAND 04 SANDY CLAY
448	502	01 CLAY 04 SANDY CLAY 29 ROCK & SAND
502	509	04 SANDY CLAY 07 FINE SAND
509	522	28 ROCK 04 SANDY CLAY 07 FINE SAND
522	523	20 LIMESTONE
523	540	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/07/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/21/95 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruno Reichmann