



<b>1 LOCATION OF WATER WELL:</b> County: <b>Meade</b>		Fraction <b>SW 1/4 SW 1/4 SE 1/4</b>	Section Number <b>15</b>	Township Number <b>T 32 S</b>	Range Number <b>R 30 E/W</b>																																																																		
Distance and direction from nearest town or city street address of well if located within city? <b>1/2 Mile East of Plains, Kansas</b>																																																																							
<b>2 WATER WELL OWNER:</b> RR#, St. Address, Box # : City, State, ZIP Code :		<b>Eagle Drilling</b> <b>260 N. Rock Road</b> <b>Wichita, Ks. 67131</b> Board of Agriculture, Division of Water Resources Application Number: <b>---</b>																																																																					
<b>3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:</b> <div style="text-align: center;"></div>		<b>4 DEPTH OF COMPLETED WELL: 306 ft. ELEVATION: Upland</b> Depth(s) Groundwater Encountered 1. <b>190</b> ft. 2. <b>220</b> ft. 3. <b>320</b> ft. WELL'S STATIC WATER LEVEL <b>185</b> ft. below land surface measured on mo/day/yr <b>Dec. 1, 1982</b> Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm Est. Yield <b>75</b> gpm: Well water was _____ ft. after _____ hours pumping _____ gpm Bore Hole Diameter <b>9 7/8</b> in. to <b>306</b> ft. and _____ in. to _____ ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot <b>XX</b> Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well Was a chemical/bacteriological sample submitted to Department? Yes _____ No <b>XX</b> ; If yes, mo/day/yr sample was submitted _____ Water Well Disinfected? Yes <b>XXX</b> No _____																																																																					
<b>5 TYPE OF BLANK CASING USED:</b> 1 Steel <b>XXX</b> PVC 3 RMP (SR) 4 ABS Blank casing diameter <b>5</b> in. to <b>266</b> ft., Dia. _____ in. to _____ ft., Dia. _____ in. to _____ ft. Casing height above land surface <b>12</b> in., weight <b>2.8</b> lbs./ft. Wall thickness or gauge No. <b>265</b>		5 Wrought iron 8 Concrete tile CASING JOINTS: Glued <b>XX</b> Clamped _____ 6 Asbestos-Cement 9 Other (specify below) Welded _____ 7 Fiberglass _____ Threaded _____																																																																					
TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) _____ 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)		SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped <b>XXX</b> Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) _____																																																																					
SCREEN-PERFORATED INTERVALS: From <b>266</b> ft. to <b>306</b> ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft.		GRAVEL PACK INTERVALS: From <b>14</b> ft. to <b>306</b> ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft.																																																																					
<b>6 GROUT MATERIAL:</b> <b>XXX</b> Neat cement 2 Cement grout 3 Bentonite 4 Other _____ Grout Intervals: From <b>4</b> ft. to <b>14</b> ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft.		What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage <b>XX5</b> <del>Oil well</del> Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage _____ Direction from well? <b>East</b> How many feet? <b>100</b>																																																																					
<table border="1" style="width:100%; border-collapse: collapse;"><thead><tr><th>FROM</th><th>TO</th><th>LITHOLOGIC LOG</th></tr></thead><tbody><tr><td>0</td><td>4</td><td>Topsoil</td></tr><tr><td>4</td><td>51</td><td>Caliche</td></tr><tr><td>51</td><td>55</td><td>Med. Sand</td></tr><tr><td>55</td><td>97</td><td>Caliche</td></tr><tr><td>97</td><td>158</td><td>Med. Sand</td></tr><tr><td>158</td><td>170</td><td>Clay</td></tr><tr><td>170</td><td>185</td><td>Fine Sand</td></tr><tr><td>185</td><td>190</td><td>Clay</td></tr><tr><td>190</td><td>217</td><td>Fine Sand</td></tr><tr><td>217</td><td>220</td><td>Clay</td></tr><tr><td>220</td><td>320</td><td>Med. Sand</td></tr></tbody></table>		FROM	TO	LITHOLOGIC LOG	0	4	Topsoil	4	51	Caliche	51	55	Med. Sand	55	97	Caliche	97	158	Med. Sand	158	170	Clay	170	185	Fine Sand	185	190	Clay	190	217	Fine Sand	217	220	Clay	220	320	Med. Sand	<table border="1" style="width:100%; border-collapse: collapse;"><thead><tr><th>FROM</th><th>TO</th><th>LITHOLOGIC LOG</th></tr></thead><tbody><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr></tbody></table>				FROM	TO	LITHOLOGIC LOG																											
FROM	TO	LITHOLOGIC LOG																																																																					
0	4	Topsoil																																																																					
4	51	Caliche																																																																					
51	55	Med. Sand																																																																					
55	97	Caliche																																																																					
97	158	Med. Sand																																																																					
158	170	Clay																																																																					
170	185	Fine Sand																																																																					
185	190	Clay																																																																					
190	217	Fine Sand																																																																					
217	220	Clay																																																																					
220	320	Med. Sand																																																																					
FROM	TO	LITHOLOGIC LOG																																																																					
<b>7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION:</b> This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <b>December 1, 1982</b> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <b>252</b> This Water Well Record was completed on (mo/day/year) <b>December 8, 1982</b> under the business name of <b>Friesen Windmill &amp; Supply Inc.</b> by (signature) 																																																																							
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.																																																																							

OFFICE USE ONLY

T

38

R

30

END

SEC.

15

SW 1/4

SW 1/4

SW 1/4

SW 1/4

SW 1/4