


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Meade	Fraction SW 1/4 NW 1/4 SE 1/4	Section number 20	Township number T 32 S	Range number R 30 E/W
2. Distance and direction from nearest town or city: 1 Mile south 1/2 West of Plains, Kansas. Street address or well location if in city:				3. Owner of well: Holmes Carol Bender R.R. or street: City, state, zip code: Plains, Kansas		
4. Locate with "X" in section below: Sketch map:  1769' N of SW corner of the SE 1/4, Sec. 20, T32S, R30W, Meade County, Kansas.				6. Bore hole dia. 28 in. Completion date 10-29-76 Well depth 435 ft.		
5. Type and color of material				From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
Top soil				0	3	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
Tan clay				3	56	9. Casing: Material Stl. Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 37 lbs./ft. Dia. 16 in. to 208 depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 219
Fine to coarse sand				56	60	10. Screen: Manufacturer's name Foster, Doerr Type Millslot, louver 16" Slot/gauze 1/8" Length 232 Set between 203 ft. and 435 ft. <input type="checkbox"/> ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material 3.4 mm
Tan clay and caliche				60	112	11. Static water level: <input type="checkbox"/> mo./day/yr. 190 ft. below land surface Date 6-26-76
Fine to coarse sand fine gravel small clay streaks				112	300	12. Pumping level below land surfaces: 218 ft. after 1/2 hrs. pumping 1837 g.p.m. 226 ft. after 1 hrs. pumping 2356 g.p.m. Estimated maximum yield 3500 g.p.m.
Fine to coarse sand blue clay streaks				300	350	13. Water sample submitted: <input type="checkbox"/> mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date
Fine to coarse sand fine to medium gravel				350	400	14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade
Tan sandy clay limestone				400	432	15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.
Tan sandy clay and limestone				440	500	16. Nearest source of possible contamination: Unk ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
(Use a second sheet if needed)						17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Layne & Bowler Model number 14TL HP 200 Volts 460 Length of drop pipe 300 ft. capacity 2250 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne-Western Co., Inc. 102 Business name Garden City, Kansas 67846 Address Signed [Signature] Date 10/29/76 Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5