

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 088 SEWARD	NW 1/4 NW 1/4 NW 1/4	36	T 32 S	R 31 W

Distance and direction from nearest town or city street address of well if located within city?

FROM LIBERAL; APPX 2 1/2 MILES EAST & 1 MILE NORTH

2 WATER WELL OWNER:	CARMEN FRANCIS	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	1205 S. WASHINGTON	Application Number:
City, State, ZIP code :	LIBERAL, KS 67901-	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 437 ELEVATION: 0																																																						
<table border="1"> <tr> <td>/ \</td> <td>X</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>1</td> <td>---</td> <td>NW</td> <td>---</td> <td>NE</td> <td>---</td> </tr> <tr> <td>M</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>i</td> <td>W</td> <td>---</td> <td>---</td> <td>---</td> <td>E</td> </tr> <tr> <td>1</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>e</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>---</td> <td>SW</td> <td>---</td> <td>SE</td> <td>---</td> </tr> <tr> <td>\ /</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>---</td> <td>---</td> <td>---</td> <td>---</td> <td>---</td> <td>---</td> </tr> </table>	/ \	X					1	---	NW	---	NE	---	M						i	W	---	---	---	E	1						e							---	SW	---	SE	---	\ /						---	---	---	---	---	---	Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft. WELL'S STATIC WATER LEVEL 245 ft. below land surface measured on mo/day/yr 05/15/07 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 10 in. to 437 ft., and in. to 0 ft. WELL WATER TO BE USED AS: 10 MONITORING Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes
/ \	X																																																						
1	---	NW	---	NE	---																																																		
M																																																							
i	W	---	---	---	E																																																		
1																																																							
e																																																							
	---	SW	---	SE	---																																																		
\ /																																																							
---	---	---	---	---	---																																																		

5 TYPE OF BLANK CASING USED: 02 PVC	CASING JOINTS: GLUED
Blank casing diameter 5 in. to 437 ft., Dia in. to 0 ft., Dia in. to 0 ft.	
Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265	
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC	
SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT	
SCREEN PERFORATED INTERVALS:	From 417 ft. to 437 ft., From 337 ft. to 357 ft.
	From 377 ft. to 397 ft., From 297 ft. to 317 ft.
GRAVEL PACK INTERVALS:	From 5 ft. to 537 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 0 ft. to 5 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: NONE OBSERVED
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	36	04 SANDY CLAY 20 LIMESTONE			
36	49	07 FINE SAND 08 MEDIUM SAND			
49	68	04 SANDY CLAY 20 LIMESTONE			
68	78	05 SAND			
78	81	04 SANDY CLAY			
81	103	05 SAND 13 FINE GRAVEL 01 CLAY			
103	137	04 SANDY CLAY 05 SAND			
137	270	05 SAND 13 FINE GRAVEL 01 CLAY			
270	283	04 SANDY CLAY			

RECEIVED
DEC 17 2007
BUREAU OF WATER

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/17/07 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 09/27/07
under the business name of HENKLE DRILLING & SUPPLY by (signature)

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
completed on (mo/day/year) 05/17/07 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 09/27/07
under the business name of HENKLE DRILLING & SUPPLY bv (signature) *[Signature]*