

Elite Irrigation & Drilling Inc

Po box 1348 Liberal, KS 67905

Test Hole Drilling Log

Customer: Scott Reiss
22958 Hwy 160
Plains, KS 67869
County: Seward

Date: 04/09/2019 Phone: -
E-Logg: no Test #: 1
Driller: Mauricio

Quarter: SW SW SW Section: 14 Township: 32s Range: 31w
GPS Location: 37.2573° -100.6714°
Total Pay: 175' Total Depth: 500'

Description of Strata from the surface down.

(example: 3-50, 47. Sand; Footage is from 3-50 feet, pay = 47. Sand is the strata description.)

0-5. Top soil
5-16. Fine sand
16-92. Fine sand clay mix
92-110. Coarse sand small gravel
110-175. Coarse sand clay strips (very small strips)
175-262. Coarse sand small gravel strips
262-345, 75. Coarse sand
345-372, 20. Medium sand clay strips
372-438, 66. Coarse sand
438-450, 9. medium sand clay strips (tight clay)
450-465. Tight clay
465-475, 5. Medium sand clay mix
475-490. Caliche sand stone mix
490-500. Red bed