

MILLER
GEARHEAD & PUMP
REPAIR, INC.

P.O. BOX 711
2707 W. JONES

GARDEN CITY, KANSAS 67846

OCT 25 1989
DIVISION OF
ENVIRONMENT
OFC. (316) 275-9618
TOLL FREE 1-800-742-9510

TEST DRILLING LOG NO: 1

NAME: First National Bank of Hutchinson
John Collingwood
% Stan Smith

LEGAL: SE $\frac{1}{4}$ 3-32-31

LOCATION: 100' SE of Old Well

COUNTY: Seward

DATE: 05-30-89

DRILLER: Bruce McIntyre

FEET		DESCRIBE FORMATION
FROM	TO	
0	3	Top Soil
3	50	Yellow Clay
50	66	Coarse Sand, Small Gravel
66	89	Yellow Clay
89	166	Fine to Medium Sand, Few Clay
166	176	Yellow Clay
176	184	Fine to Medium Sand
184	188	Yellow Clay
188	218	Fine to Medium Sand
218	224	Yellow Clay
224	248	Fine to Medium Sand, Clay Streaks
248	284	Fine Sand
284	286	Blue Clay
286	316	Coarse Blue Sand
316	336	Fine Blue Sand, Dirty
336	370	Fine to Coarse Sand, Clay Streaks
370	382	Sandy Clay
382	390	Coarse Sand
390	482	Sandy Clay, Sand Streaks
482	512	Fine Sand, Clay Streaks
512	528	Sandy Clay, Sand Streaks
528	532	Hard White Rock
532	550	Red Bed

TOTAL DEPTH OF TEST HOLE: 550 feet

WORTHINGTON PUMP DISTRIBUTOR
"KEEP ON PUMPING"