



DRILLERS TEST LOG

CUSTOMERS NAME Darrell Langhofer DATE 12-1-75  
 STREET ADDRESS \_\_\_\_\_ TEST # 3 E-Log-500'  
 CITY & STATE Plains, KS DRILLER Rector  
 COUNTY Seward QUARTER NE SECTION 10 TOWNSHIP 32 RANGE 31

LOCATION 100' south of Test #2

%	DRILLED FOOTAGE			Description of Strata	WELL LOCATION	
	From	Pay	To		Static Water Level	Proposed Well Depth
	0		3	Top soil		
	3		40	Brown sandy clay		
	40		72	Sand fine to med coarse & small gravel		
	72		85	Brown clay & caliche		
	85		129	Sand, gravel, & few small clay sts.		
	129		140	Brown clay (sticky)		
	140		159	Sand & gravel		
	159		180	Brown clay		
	180		194	Sand & gravel		
	194		216	Brown clay		
60	216	21	237	Sand & gravel, loose, used lots of water.		
	237		240	Sandy brown clay		
65	240	11	251	Sand & gravel, loose, used water.		
	251		260	Brown sandy clay & sand fine to med		
	260		277	Blue clay		
30	277	3	280	Blue sand, fine to med coarse		
	280		288	Blue clay		
40	288	42	330	Sand med coarse & few sandy blue clay sts, blue clay & limerock sts.		
65	330	50	380	Sand & gravel (loose), used lots of water.		
	380		390	Brown clay & limerock		
40	390	5	395	Sand & gravel, used water.		
45	395	40	435	Brown clay, limerock & coarse sts of sand & gravel		
70	435	50	485	Sand fine to med coarse, small gravel, clay & limerock sts, used water.		
	485		495	Brown clay & limerock		
	495		500	Red shale		
TOTAL DEPTH OF WELL 487'						
Set up facing south						
Dig pit on the west						