

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County <b>Seward</b>	Fraction <b>NE<sup>1</sup>/<sub>4</sub> SW<sup>1</sup>/<sub>4</sub> SW<sup>1</sup>/<sub>4</sub></b>	Section number <b>28</b>	Township number T <b>32</b>	Range number S R <b>32</b>	<b>E W</b>
2. Distance and direction from nearest town or city: <b>1 1/2 W of Liberal, Kansas</b> Street address of well location if in city:			3. Owner of well: <b>Wayne Wettstein</b> R.R. or street: <b>R.R.</b> City, state, zip code: <b>Liberal, Kansas 67901</b>			
4. Locate with "X" in section below: <div style="text-align: center;">N NW NE SW SE S W E 1 Mile</div>			Sketch map: <div style="text-align: center;"><b>Center of the SW<sup>1</sup>/<sub>4</sub>, Sec. 28, T32S, R32W, Seward County, Kansas.</b></div>			
5. Type and color of material			From	To		
<b>Tan clay</b>			<b>0</b>	<b>60</b>	<b>Millslot, louver</b>	
<b>Fine to coarse sand fine gravel</b>			<b>60</b>	<b>180</b>	<b>Type Dia. 16"</b>	
<b>Fine to medium sand, small clay streaks loose</b>			<b>180</b>	<b>310</b>	<b>Slot/gauze 1/8" Length 180</b>	
<b>Fine sand small clay streaks, loose</b>			<b>310</b>	<b>430</b>	<b>Set between 250 ft. and 430 ft.</b>	
<b>Red bed</b>			<b>430</b>	<b>440</b>	<b>Gravel pack? x Size range of material 2.5 mm</b>	
					11. Static water level: _____ mo./day/yr. <b>200</b> ft. below land surface Date <b>1-22-77</b>	
					12. Pumping level below land surfaces: <b>220</b> ft. after <b>1 1/2</b> hrs. pumping <b>1080</b> g.p.m. <b>238</b> ft. after <b>1</b> hrs. pumping <b>1943</b> g.p.m. Estimated maximum yield <b>2500</b> g.p.m.	
					13. Water sample submitted: _____ mo./day/yr. Yes <b>x</b> No Date _____	
					14. Well head completion: Pitless adapter <b>x</b> Inches above grade _____	
					15. Well grouted? <b>yes</b> With: Neat cement <b>x</b> Bentonite Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.	
					16. Nearest source of possible contamination: <b>unk</b> ft. Direction Type Well disinfected upon completion? <b>x</b> Yes No	
					17. Pump: Manufacturer's name <b>Layne &amp; Bowler</b> Not installed Model number <b>12KH</b> HP Volts Length of drop pipe <b>300</b> ft. capacity <b>1000</b> g.p.m. Type: Submersible <b>x</b> Turbine Jet Reciprocating Centrifugal Other	
(Use a second sheet if needed)						
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Layne-Western Co., Inc. 102</b> Business name License No. Address <b>Garden City, Kansas</b> Signed <b>[Signature]</b> Date <b>9 Jun 77</b> Authorized representative			