

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 088 SEWARD ; NW 1/4 SW 1/4 NE 1/4 ; 20 ; T 32 S ; R 33 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 12 1/2 MILES NORTH, & 1/2 WEST OF LIBERAL

2 WATER WELL OWNER: SUPREME FEEDERS CO.
 RR#, St. Address, Box # : P. O. BOX 708 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : LIBERAL, KS 67901- Application Number: 41,286

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 215 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 45 ft. below land surface measured on mo/day/yr 10/31/96
 Pump testdata: Well water was 74 ft. after 4 hours pumping 1410 gpm
 Estimated Yield 1410 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 215 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 12 in. to 215 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 82 ft. to 212 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 210 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	4	02 SILT 01 CLAY 05 SAND			
4	10	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
10	30	05 SAND 11 GRAVEL			
30	36	01 CLAY 04 SANDY CLAY			
36	45	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
45	63	05 SAND 04 SANDY CLAY			
63	96	05 SAND 04 SANDY CLAY			
96	101	01 CLAY 04 SANDY CLAY 05 SAND			
101	182	05 SAND 11 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/28/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/31/96 by (signature) HENKLE DRILLING & SUPPLY

