


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Seward	Fraction SW 1/4 NE 1/4 SW 1/4	Section number 8	Township number T 32 S R 33 E/W	Range number 33
2. Distance and direction from nearest town or city: 18 Miles north Street address of well location if in city: & 2 west of Liberal				3. Owner of well: Franz Land Company R.R. or street: Box 606 City, state, zip code: Liberal, Kansas 67901		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 28 in. Completion date 11-10-75 Well depth 338 ft.		
		Well drilled near TH 15-75 which is located in the center of the SW 1/4, Sec. 8, T32S, R33E Seward County, Kansas		7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
5. Type and color of material		From	To	8. Use: Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation Air conditioning <input type="checkbox"/> Stock Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Sandy soil		0	2	9. Casing: Material steel Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 37 lbs./ft.		
Fine to coarse sand medium to coarse gravel		2	66	Dia. 16 in. to 158 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 219		
Coarse sand and gravel with yellow clay		66	82	10. Screen: Manufacturer's name Foster & Doerr Millislot & louver 16" Type <input type="checkbox"/> Dia. <input type="checkbox"/> Slot/gauze 1/8" Length 180' Set between 158 ft. and 338 ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material 2.5-9.2mm		
Fine to coarse sand medium to coarse gravel		82	158	11. Static water level: <input type="checkbox"/> mo./day/yr. 88 ft. below land surface Date 10-28-75		
Fine to coarse sand medium to coarse gravel				12. Pumping level below land surfaces: 98 ft. after 1/2 hrs. pumping 1040 g.p.m. 120 ft. after 1 hrs. pumping 3,000 g.p.m. Estimated maximum yield 3,000 g.p.m.		
with tan clay		158	161	13. Water sample submitted: <input type="checkbox"/> mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date <input type="checkbox"/>		
Fine to coarse sand medium to coarse gravel		161	201	14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade		
Fine to coarse sand medium gravel		201	319	15. Well grouted? <input checked="" type="checkbox"/> With: Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete <input type="checkbox"/> Depth: From 0 ft. to 10 ft.		
Coarse sand medium gravel with yellow clay streaks		319	338	16. Nearest source of possible contamination: unk ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
Blue and tan clay		338	380	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Layne & Bowler Model number 12K HP 100 Volts <input type="checkbox"/> Length of drop pipe 180 ft. capacity 900 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne-Western Co., Inc. 150 Business name License No. <input type="checkbox"/> Address Garden City, Ks. Signed [Signature] Date 1 Dec 75 Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5