

# Elite Irrigation & Drilling Inc

Po box 1848 Liberal, KS 67905

## Test Hole Drilling Log

Customer: Jeanette Shepherd  
4224 Shiloh Ave  
Enid, OK 73703

Date: 2019-05-01 Phone: -  
E-Logg: No Test #: 1

Driller: Mauricio

County: Seward

Quarter: NW NW NW Section: 16 Township: 32s Range: 34w

GPS Location: 37.2641° -101.0312°

Total Pay: 210' Total Depth: 520'

Description of Strata from the surface down.

(example: 3-50, 47. Sand; Footage is from 3-50 feet, pay = 47. Sand is the strata description.)

0-5. Top soil  
5-18. Fine sand  
18-25. Caliche fine sand mix  
25-65. Clay sand mix  
65-132. Clay  
132-211. Coarse sand gravel mix  
211-227. Coarse sand clay strips  
227-262. Coarse sand  
262-295. Coarse sand small clay strips  
295-342, 42. Coarse sand  
342-505, 163. Coarse sand gravel mix  
505-515, 5. Gravel clay mix  
515-520. Red bed