

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment (Water well Contractors) Topeka, Kansas 66620

1. Location of well:		County Seward	Fraction SW 1/4 NE 1/4 SW 1/4	Section number 35	Township number T 32 S R 34 E/W	Range number 34
2. Distance and direction from nearest town or city: 11 North and 4 west of Liberal Street address of well location if in city:			3. Owner of well: Dwayne Reeve R.R. or street: R.R. City, state, zip code: Liberal, Kansas			
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile			Sketch map: 740' North of center of the SW 1/4, Sec. 35, T32S, R34W, Seward County, Kansas.		6. Bore hole dia. 28 in. Completion date 2-24-76 Well depth 351 ft.	
5. Type and color of material			From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
Top soil			0	6	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
Brown clay			6	119	9. Casing: Material Stl. Height: <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 37 lbs./ft. Dia. 16 in. to 187 ft. depth; Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth; gage No. .219	
Fine to coarse sand			119	140	10. Screen: Manufacturer's name Foster, Doerr Type Milslot, lower 16" Slot/gauze 1/8" Length 16" Set between 187 ft. and 351 ft. <input type="checkbox"/> ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material 4.4 mm	
Tan clay			140	152	11. Static water level: <input type="checkbox"/> mo./day/yr. 164 ft. below land surface Date 6-7-76	
Fine to coarse sand small clay streaks			152	260	12. Pumping level below land surfaces: 170 ft. after 1/2 hrs. pumping 1016 g.p.m. 176 ft. after 1 hrs. pumping 2230 g.p.m. Estimated maximum yield 2300 g.p.m.	
Tan clay sand streaks			260	280	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____	
Fine to coarse sand clay streaks			280	351	14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade	
Mixed colored clay sand streaks			351	398	15. Well grouted? yes With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.	
Red bed			398	420	16. Nearest source of possible contamination: Unk ft. _____ Direction _____ Type _____ Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
(Use a second sheet if needed)					17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Layne & Bowler Model number 12KL HP _____ Volts _____ Length of drop pipe 260 ft. capacity 800 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne-Western Co., Inc. 102 Business name License No. _____ Address Garden City, Kansas Sign: <i>[Signature]</i> Date 18/Nov-76 Authorized representative			
Topography: <input checked="" type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley						

T 32 S R 34 E Sec 35 SW 1/4 NE 1/4 SW 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5