

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: STEVENS NE 1/4 NE 1/4 NW 1/4 13 T 32 S R 35 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM MOSCOW, KS - 3 1/2 ON BLACK TOP - 7 EAST ON BLACK TOP

2 WATER WELL OWNER: KANCO PROPERTIES  
 RR#, St. Address, Box #: P.O. BOX 507 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: LA VETA, CO 81055- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

		X	
	NW	NE	
W			E
	SW	SE	

4 DEPTH OF COMPLETED WELL 486 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 282 ft. below land surface measured on mo/day/yr 10/04/95  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 40 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 in. to 486 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;  
 if yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLOUED  
 Blank casing diameter 5 in. to 486 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21

TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 340 ft. to 360 ft., From 440 ft. to 480 ft.  
 From 280 ft. to 400 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 25 ft. to 486 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: ABANDONED WELL  
 Direction from well? NORTH How many feet? 25

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	40	TOPSOIL FINE SAND CLAY			
40	80	FINE SAND CLAY LAYERS CLAY			
80	100	CLAY FINE - MED SAND IN LAYERS			
100	140	FINE - MED SAND CLAY TAN IN COLOR			
140	160	CLAY IN LAYERS MEDIUM SAND			
160	280	FINE SAND COARSE SAND			
280	300	COARSE SAND CLAY LAYERS			
300	320	COARSE SAND CLAY ROCK LAYERS			
320	340	COARSE SAND CLAY LAYERS			
340	360	FINE SAND CLAY LAYERS			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 10/06/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 10/12/95 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Jared Ault*

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: STEVENS NE 1/4 NE 1/4 NW 1/4 13 T 32 S R 35 W

2 WATER WELL OWNER: KANCO PROPERTIES  
 RR#, St. Address, Box #: P.O. BOX 507 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: LA VETA, CO 81055- Application Number:

FROM	TO	LITHOLOGIC LOG
360	380	CLAY FINE SAND IN LAYERS
380	400	CLAY THIN ROCK LAYER FINE - MED SAND
400	420	CLAY FINE - MED SAND IN LAYERS
420	440	CLAY FINE SAND IN LAYERS
440	460	CLAY FINE - MED SAND THIN ROCK LAYER
460	475	FINE SAND SANDSTONE
475	500	REN REN