

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 095 STEVENS NW 1/4 NW 1/4 NE 1/4 27 T 32 S R 36 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM MOSCOW; APPX 5 1/2 MILES SOUTH

2 WATER WELL OWNER: BRYNE SULLINS Board of Agriculture, Division of Water Resources  
 RR#, St. Address, Box #: RR 1 BOX 43 Application Number: 44,137  
 City, State, ZIP code: MOSCOW, KS 67952-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 487 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \		X			
1	--- NW ---	--- NE ---			WELL'S STATIC WATER LEVEL 275 ft. below land surface measured on mo/day/yr 10/12/04 Pump test data: Well water was 329 ft. after 4 hours pumping 1500 gpm
M i l l e	W ---	---	E		Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
\ /	---	SW ---	SE ---		Bore Hole Diameter 24 in. to 487 ft., and in. to 0 ft.
					WELL WATER TO BE USED AS: 02 IRRIGATION
					Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 487 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 330 ft. to 360 ft., From 0 ft. to 0 ft.  
 From 392 ft. to 482 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 487 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	33	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
33	58	04 SANDY CLAY			
58	122	05 SAND 13 FINE GRAVEL 01 CLAY			
122	128	05 SAND 11 GRAVEL			
128	137	04 SANDY CLAY			
137	160	05 SAND 13 FINE GRAVEL 01 CLAY			
160	209	04 SANDY CLAY			
209	226	05 SAND 01 CLAY			
226	279	04 SANDY CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/08/04 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/11/05  
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:      Fraction      Section Number      Township Number      Range Number  
COUNTY: 095 STEVENS      NW 1/4 NW 1/4 NE 1/4      27      T 32 S      R 36 W

2 WATER WELL OWNER:      BRYNE SULLINS  
RR#, St. Address, Box # :      RR 1 BOX 43      Board of Agriculture, Division of Water Resources  
City, State, ZIP code :      MOSCOW, KS 67952-      Application Number: 44,137

FROM	TO	LITHOLOGIC LOG
279	285	07 FINE SAND 08 MEDIUM SAND 01 CLAY
285	316	04 SANDY CLAY
316	322	05 SAND 13 FINE GRAVEL 01 CLAY
322	330	04 SANDY CLAY 05 SAND
330	357	05 SAND 11 GRAVEL 01 CLAY
357	362	05 SAND 01 CLAY
362	395	01 CLAY
395	482	05 SAND 01 CLAY
482	494	01 CLAY 05 SAND
494	555	01 CLAY
555	575	01 CLAY 05 SAND
575	580	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/08/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145      This Water Well Record was completed on (mo/day/yr) 01/11/05 under the business name of HENKLE DRILLING & SUPPLY      by (signature)

*Bruce J. Reichert*