

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 095 STEVENS SE 1/4 NE 1/4 NW 1/4 24 T 32 S R 37 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM HUGOTON; APPX 4 3/4 MILES NORTH & 2 MILES EAST

2 WATER WELL OWNER: SUNBELT FEEDERS, INC.
 RR#, St. Address, Box # : PO BOX 38 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : HUGOTON, KS 67951-0038 Application Number: 20,484

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 357 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \	1	---	NW	X	---	NE	---
		---			---		
M i l e	W	---			---		E
		---			---		
\ /		---	SW		---	SE	---
		---			---		

WELL'S STATIC WATER LEVEL 195 ft. below land surface measured on mo/day/yr 09/19/05
 Pump test data: Well water was 239 ft. after 4 hours pumping 220 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 17 1/2 in. to 357 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 03 FEEDLOT
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: OTHER CASING JNT - SHERLOCK
 Blank casing diameter 8 in. to 357 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 7 lbs/ft. Wall thickness or gauge No. .410
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 227 ft. to 267 ft., From 0 ft. to 0 ft.
 From 337 ft. to 357 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 357 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	05 SAND			
2	49	07 FINE SAND 04 SANDY CLAY			
49	71	05 SAND 11 GRAVEL			
71	84	04 SANDY CLAY			
84	97	05 SAND			
97	100	04 SANDY CLAY			
100	134	05 SAND 13 FINE GRAVEL			
134	200	04 SANDY CLAY 20 LIMESTONE 05 SAND			
200	215	07 FINE SAND 08 MEDIUM SAND			
215	224	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/13/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/28/05 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: COUNTY: 095 STEVENS	Fraction SE 1/4 NE 1/4 NW 1/4	Section Number 24	Township Number T 32 S	Range Number R 37 W
--	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: SUNBELT FEEDERS, INC.
 RR#, St. Address, Box # : PO BOX 38 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : HUGOTON, KS 67951-0038 Application Number: 20,484

FROM	TO	LITHOLOGIC LOG
224	231	05 SAND
231	236	04 SANDY CLAY
236	269	05 SAND 13 FINE GRAVEL 01 CLAY
269	337	04 SANDY CLAY 07 FINE SAND
337	354	05 SAND
354	395	04 SANDY CLAY 07 FINE SAND
395	400	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/13/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/28/05 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Brian J. Henkle*