



*Keefer Farms #3*

CUSTOMER'S NAME (3 W Land and Cattle Company) DATE 1-6-75  
 STREET ADDRESS % Walter Beasley TEST # 1 E.L.Hole  
 CITY & STATE Box 156, Hugoton, Kansas DRILLER Livingston  
 COUNTY Stevens QUARTER NW SECTION 14 TOWNSHIP 32 RANGE 38

LOCATION 40 Ft. North of Pivot

WELL LOCATION well #3

DEPTH	DROPPED FROM	POSTAGE PAY	FOOTAGE TO	Description of Strata	Static Water Level
					Proposed Well Depth
	0		6	Blow sand	
	6		100	Clay and few fine sand st.	
	100		110	Sand fine to med. coarse	
	110		122	Limerock, cemented sand	
	122		180	Brown clay, few limerock ledges, fine sand st.	
	180		220	Sand fine clay and limerock st.	
60	220	46	266	Sand fine to med. coarse, small brown gravel, few clay, limerock st.	
	266		278	Brown sandy clay, few sand st.	
55	278	28	306	Sand fine to med. coarse, small gravel.	
NS	306		367	Very fine sand and clay	
	367		400	Brown sandy clay and fine sand st.	
	400		470	Brown sandy clay, sand fine to med. coarse, few, small gravel. st.	
70	470	76	546	Sand fine to med. coarse, small brown gravel and few white rock	
	546		550	Red bed.	

150

TOTAL DEPTH OF WELL 548 FT.

set up West; dig pit on the North.