

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

CWW Inv. #15323

Stout C-#1

1. Location of well:	County <b>Stevens</b>	Fraction <b>CN 1/4 SE 1/4 NE 1/4</b>	Section number <b>32</b>	Township number <b>T 32S S R 38W</b>	Range number <b>E/W</b>
2. Distance and direction from nearest town or city: <b>From Hugoton Elev. go 6m West on Blacktop - 2 3/4m North &amp; Street address of well location if in city: West to location.</b>			3. Owner of well: <b>Anadarko Production Company</b> R.R. or street: <b>c/o P. Gatlin, Box 351</b> City, state, zip code: <b>Liberal, Kansas 67901</b>		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>9</u> in. Completion date <u>12-26</u> Well depth <u>400</u> ft.	
		<p style="text-align: center;"><i>West to Loc. on Blacktop</i></p> <p style="text-align: center;"><i>Hugoton</i></p>		7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
				8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input checked="" type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input checked="" type="checkbox"/> Oil field water <input type="checkbox"/> Other	
5. Type and color of material			From	To	9. Casing: Material _____ Height: Above or below Threaded _____ Welded _____ Surface <u>28</u> in. RMP _____ PVC <input checked="" type="checkbox"/> Weight <u>2.78</u> lbs./ft. Dia. <u>5</u> in. to <u>320</u> ft. depth   Wall Thickness: inches or Dia. _____ in. to _____ ft. depth   gage No. <u>265</u>
Surface			0	2	10. Screen: Manufacturer's name _____ <b>Sawed</b>
Clay			2	26	Type <u>PVC</u> Dia. <u>5"</u> Slot/gauze _____ Length <u>80'</u> Set between <u>320</u> ft. and <u>400</u> ft. _____ ft. and _____ ft.
Clay & medium to large sand 40-60			26	40	Gravel pack? <input checked="" type="checkbox"/> yes Size range of material <u>1/8-3/16</u>
Clay			40	56	11. Static water level: _____ mo./day/yr. <u>170</u> ft. below land surface Date <u>12-26-78</u>
Fine sand			56	75	12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <u>60</u> g.p.m.
Medium to large sand			75	83	13. Water sample submitted: _____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____
Clay & medium to large sand 85-15			83	115	14. Well head completion: <input type="checkbox"/> Pitless adapter <u>=28</u> inches above grade
Fine sand			115	142	15. Well grouted? <input checked="" type="checkbox"/> yes With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.
Clay & fine sand 90-10			142	150	16. Nearest source of possible contamination: ft. <u>100</u> Direction <u>NE</u> Type <u>oilwell</u>
Clay			150	267	Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
Clay & fine sand 70-30			267	328	17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
Clay & fine sand 30-70			328	335	
Medium to large sand			335	400	
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Carlile Water Well Service 118</b> Business name _____ License No. _____ Address <u>Box AA, Liberal, KS</u> Signed <u>Edward C. Means</u> Date <u>12-29</u> Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley					

32  
 38  
 32  
 32  
 CN SE NE  
 1/4 1/4 1/4