

WATER WELL RECORD Form WWC-5 KSA 82a-1212

LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: MORTON NB 1/4 NE 1/4 SW 1/4 16 T 32 S R 39 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM ROLLA ON HIGHWAY 51 - 14N, 3E, 1/2 AND 1/2 MILES EAST

WATER WELL OWNER: BOZONE, DAVID
 RR#, St. Address, Box #: HC02 - BOX 64 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: ROLLA, KS 67954- Application Number:

LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 385 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 193 ft. below land surface measured on no/day/yr 11/09/04
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 40 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 325 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 325 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 240 ft. to 320 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 325 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 02 PINE SAND			
20	40	02 PINE SAND 14 WHITE CLAY			
40	60	14 WHITE CLAY 02 PINE SAND			
60	80	10 PINE-MEDSAND			
80	100	10 PINE-MEDSAND 32 TAN CLAY			
100	140	32 TAN CLAY			
140	160	32 TAN CLAY 02 PINE SAND 19 LAYERS			
160	180	02 PINE SAND 32 TAN CLAY			
180	200	32 TAN CLAY 10 PINE-MEDSAND			
200	220	32 TAN CLAY 10 PINE-MEDSAND 19 LAYERS			

CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (no/day/year) 11/10/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 12/10/04 under the business name of JOB'S WELL SERVICE, INC. by (signature) Judith Cwick

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: HORTON	NE 1/4 NE 1/4 SW 1/4	16	T 32 S	R 39 W

WATER WELL OWNER:	BOZONE, DAVID	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	HC02 - BOX 64	Application Number:
City, State, ZIP code :	ROLLA, KS 67954-	

FROM	TO	LITHOLOGIC LOG
220	240	32 TAN CLAY 24 THINROCLAYER 35 CALACHIE
240	260	32 TAN CLAY 35 CALACHIE 29 SANDSTONE
260	320	29 SANDSTONE
320	340	08 ROCK LAYERS 11 BROWN CLAY 05 CLAY

CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/10/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 12/10/04 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Julitt Cook*