

DRILLERS TEST LOG

CUSTOMERS NAME Gerald Schmidt DATE 9/1/77
 STREET ADDRESS _____ TEST # 1 E. LOG Yes
 CITY & STATE Rollo, Kansas DRILLER Martinez
 COUNTY Stevens QUARTER Sw SECTION 2 TOWNSHIP 32 RANGE 39
 LOCATION SE corner of the 1/4.

FOOTAGE				DESCRIPTION OF STRATA	WELL LOCATION	
From	Day	To	Static Water Level _____		Proposed Well Depth _____	
		0	2	Top Soil		
		2	35	Brown clay with a few lime rock sts.		
		35	45	Sand fine to med.		
		45	50	Brown clay		
		50	61	Sand fine to med coarse.		
		61	120	Brown clay		
		120	140	Brown clay with a few lime rock sts.		
		140	180	Brown clay - sticky.		
		180	220	Brown clay - sticky - with a few lime rock sts.		
		220	241	Brown clay - sticky.		
60		241	09 250	Sand fine to med coarse, small gravel - loose. Used water. A few white rock sts with a few clay sts.		
		250	256	Cemented sand, clay sts - very hard.		
50	256	05 261	261	Sand fine to med coarse, small gravel - loose. Used water.		
		261	270	Cemented sand with a few clay sts. Very hard.		
60	270	20 290	290	Sand fine to med coarse, small gravel - loose. Used water. Very few brown rock sts.		
45	290	08 298	298	Brown rock with a few clay sts. Loose - used water.		
		298	301	Brown clay		
		301	360	Weather shale		
		360	380	Weather shale and soapstone sts.		
Fair	380	20 400	400	Soapstone, yellow sandstone sts. Loose in places - used water.		
Good	400	20 420	420	Yellow sandstone - loose - used water.		
Fair	420	21 441	441	Yellow sandstone - loose in places. Used water. A few soapstone sts.		
		441	460	Yellow soapstone.		
Fair	460	20 480	480	Yellow soapstone with a few yellow sandstone sts. Used water.		
		480	512	Soapstone.		
		512	520	Red bed - hard.		
		123			TOTAL DEPTH OF WELL 483'	
					Set up facing West	
					Pit on the North	
					(Used 3 Quik GEL)	

WELLERY, KS
 Phone 748-3278

HENKLE DRILLING & SUPPLY CO., INC.
 IRRIGATION HEADQUARTERS

SUBLETTE, KS
 Phone 675-4311

***** IRRIGATION & INDUSTRIAL WELLS ***** STOCK WELLS