

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 065 MORTON | NW 1/4 SW 1/4 SE 1/4 | 32 | T 32 S | R 41 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM RICHFIELD; APPX 2 3/4 MILES SOUTH

2 WATER WELL OWNER: ROBERT DAVIS
 RR#, St. Address, Box #: PO BOX 487 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: RICHFIELD, KS 67953-0487 Application Number: 22895

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 350 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 92 ft. below land surface measured on mo/day/yr 12/28/07
 Pump test data: Well water was 203 ft. after 4 hours pumping 598 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 350 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 350 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. 3250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 125 ft. to 345 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 350 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTH How many feet? 80

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	6	01 CLAY			
6	20	04 SANDY CLAY 31 CALICHE			
20	40	31 CALICHE 36 GYP ROCK			
40	62	01 CLAY 05 SAND			
62	86	01 CLAY			
86	98	07 FINE SAND 01 CLAY			
98	119	01 CLAY 07 FINE SAND			
119	152	07 FINE SAND			
152	165	06 VERY FN SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/20/07 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/14/08
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
COUNTY: 065 MORTON | NW 1/4 SW 1/4 SE 1/4 | 32 | T 32 S | R 41 W

2 WATER WELL OWNER: ROBERT DAVIS
RR#, St. Address, Box #: PO BOX 487 Board of Agriculture, Division of Water Resources
City, State, ZIP code: RICHFIELD, KS 67953-0487 Application Number: 22895

FROM	TO	LITHOLOGIC LOG
165	185	05 SAND 13 FINE GRAVEL 28 ROCK
185	191	04 SANDY CLAY
191	204	07 FINE SAND 01 CLAY
204	219	05 SAND
219	222	01 CLAY
222	230	23 SANDSTONE
230	243	23 SANDSTONE
243	258	23 SANDSTONE 31 CALICHE
258	262	19 SHALE
262	320	31 CALICHE 23 SANDSTONE
320	335	31 CALICHE 23 SANDSTONE
335	345	23 SANDSTONE
345	360	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/20/07 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/14/08
under the business name of HENKLE DRILLING & SUPPLY by (signature)

Brian J. Reichmuth