

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number  
 COUNTY: 013 CLARK | SW 1/4 SW 1/4 SE 1/4 | 12 | T 33 S | R 23 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM ASHLAND; APPX 1/4 MILE SOUTH

2 WATER WELL OWNER: CITY OF ASHLAND  
 RR#, St. Address, Box # : 703 MAIN Board of Agriculture, Division of Water Resources  
 City, State, ZIP code : ASHLAND, KS 67831- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 93 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 36 ft. below land surface measured on mo/day/yr 10/13/06  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 9 7/8 in. to 93 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 10 MONITORING  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: OTHER - CERTILOCK  
 Blank casing diameter 5 in. to 63 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 63 ft. to 93 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 30 ft. to 93 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 30 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
1	2	02 SILT			
2	4	01 CLAY 31 CALICHE			
4	25	01 CLAY 05 SAND			
25	40	01 CLAY 31 CALICHE			
40	48	05 SAND			
48	57	01 CLAY			
57	80	05 SAND 11 GRAVEL 28 ROCK			
80	91	07 FINE SAND 01 CLAY			
91	93	05 SAND 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/15/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/13/06 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Osam J. Reichardt*