

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 013 CLARK SW 1/4 SW 1/4 SE 1/4 12 T 33 S R 23 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM ASHLAND; APPX 1/4 MILE SOUTH

2 WATER WELL OWNER: CITY OF ASHLAND Board of Agriculture, Division of Water Resources  
 RR#, St. Address, Box #: 703 MAIN Application Number: 41184 19412 Clarke  
 City, State, ZIP code: ASHLAND, KS 67831-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 99 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 33.5 ft. below land surface measured on mo/day/yr 9/6/07  
 Pump test data: Well water was 51 ft. after 8 hours pumping 560 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 36 in. to 99 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 05 PUB. WTR SUP  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 99 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 63 lbs/ft. Wall thickness or gauge No. .375  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 03 STAINLESS ST  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 63 ft. to 93 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 40 ft. to 99 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 CEMENT GROUT Bentonite  
 Grout Intervals: From 0 ft. to 20 ft., From 20 ft. to 40 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 14 ABAND. WELL  
 Direction from well? SOUTHEAST How many feet? 180

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	4	01 CLAY 31 CALICHE			
4	25	01 CLAY 05 SAND			
25	40	01 CLAY 31 CALICHE			
40	48	05 SAND			
48	57	01 CLAY			
57	80	05 SAND 11 GRAVEL 28 ROCK			
80	91	07 FINE SAND 01 CLAY			
91	97	05 SAND 13 FINE GRAVEL			
97	104	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/31/07 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 09/27/07  
 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Richman*