

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: Meade NW 1/4 NW 1/4 SW 1/4 29 T 33 S R 28 W

Distance and direction from nearest town or city street address of well if located within city?
 9 1/2 S. 3 W.

2 WATER WELL OWNER: MARGARET BLEHM 328
 RR#, St. Address, Box #: 23130 15 RD Board of Agriculture, Division of Water Resources
 City, State, ZIP code : MEADE, KS 67864- Application Number:

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

1	2	3	4	5	6	7	8
9	10	11	12	13	14	15	16
17	18	19	20	21	22	23	24
25	26	27	28	29	30	31	32

4 DEPTH OF COMPLETED WELL 100 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 14 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 14 ft. below land surface measured on mo/day/yr
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 8.75 in. to 0 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 01 DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 80 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 80 ft. to 100 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 100 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 65 ft. to 75 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 01 SEPTIC TANK
 Direction from well? W. How many feet? 75

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	9	TAN CLAY			
9	24	05 SAND AND 17 GRAVEL			
24	53	GREY CLAY			
53	57	05 SAND AND 17 GRAVEL			
57	74	GREY CLAY			
74	100	05 SAND AND 17 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
 completed on (mo/day/year) 7 /29/95 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 08/07/95
 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse