


1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Meade		NE 1/4 NW 1/4 NE 1/4	9	T 33 S	R 28 E/W
Distance and direction from nearest town or city street address of well if located within city? 6 South, 1 1/2 W of Meade, Ks.					
2 WATER WELL OWNER:		Southwest Gas Storage			
RR#, St. Address, Box # :		Nye Route, Box 62 A		Board of Agriculture, Division of Water Resources	
City, State, ZIP Code :		Meade, Kansas 67864		FRIESEN 1-9 Application Number: -----	
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 59 ft. ELEVATION: Slope			
N W E S 		Depth(s) Groundwater Encountered 1. Not available ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL: 25 ft. below land surface measured on mo/day/yr Sep. 25, 1981			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield 30 gpm: Well water was ft. after hours pumping gpm			
Bore Hole Diameter: 7.7/8 in. to 59 ft. and in. to ft.		WELL WATER TO BE USED AS:			
1 Domestic		3 Feedlot	5 Public water supply	8 Air conditioning	11 Injection well
2 Irrigation		4 Industrial	6 Oil field water supply	9 Dewatering	12 Other (Specify below)
7 Lawn and garden only		10 Observation well			
Was a chemical/bacteriological sample submitted to Department? Yes No XX; If yes, mo/day/yr sample was submitted					
Water Well Disinfected? Yes XX No					
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued XX Clamped			
1 Steel		3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)	Welded
XX PVC		4 ABS	7 Fiberglass		Threaded
Blank casing diameter 5 in. to 20 ft. Dia in. to ft. Dia in. to ft.					
Casing height above land surface 12 in., weight 2.8 lbs./ft. Wall thickness or gauge No. 265					
TYPE OF SCREEN OR PERFORATION MATERIAL:		XX PVC			
1 Steel		3 Stainless steel	5 Fiberglass	8 RMP (SR)	11 Other (specify)
2 Brass		4 Galvanized steel	6 Concrete tile	9 ABS	12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped XX Saw cut 11 None (open hole)			
1 Continuous slot		3 Mill slot	6 Wire wrapped	9 Drilled holes	
2 Louvered shutter		4 Key punched	7 Torch cut	10 Other (specify)	
SCREEN-PERFORATED INTERVALS:		From 20 ft. to 60 ft. From ft. to ft.			
GRAVEL PACK INTERVALS:		From 14 ft. to 60 ft. From ft. to ft.			
6 GROUT MATERIAL:		XX Neat cement 2 Cement grout 3 Bentonite 4 Other			
Grout Intervals: From 4 ft. to 14 ft. From ft. to ft. From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank		4 Lateral lines	7 Pit privy	11 Fuel storage	15 Oil well/Gas well
2 Sewer lines		5 Cess pool	8 Sewage lagoon	12 Fertilizer storage	XX6 Other (specify below)
3 Watertight sewer lines		6 Seepage pit	9 Feedyard	13 Insecticide storage	Gas Storage Well
Direction from well? North		How many feet? 130			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	1	Topsoil			
1	2	Clay			
2	15	Fine Sand			
15	20	Clay			
20	50	Med. to Lar. Sand, Black w/Streaks of Clay			
50	60	Clay Red Bed			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) Sep. 25, 1981 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 252 This Water Well Record was completed on (mo/day/year) September 28, 1981 under the business name of Friesen Windmill & Supply Inc. by (signature) [Signature]					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					

OFFICE USE ONLY

T

33

R

28

EW

SEC.

9

NE 1/4

NW 1/4

SE 1/4

SW 1/4