

WATER WELL RECORD Form WWC-3 KSA 82a-1210

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 060 MEADE SW 1/4 SW 1/4 SW 1/4 19 T 33 S R 28 W

Distance and direction from nearest town or city street address of well if located within city?
 APPX. 8 MILES SOUTH, 4 MILES WEST & 1 MILE SOUTH OF MEADE

2 WATER WELL OWNER: QUICK, DAVID
 RR#, St. Address, Box #: P.O. BOX 216 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: MEADE, KS 67864- Application Number: 15,044

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
5	6	7	8
9	10	11	12

WELL'S STATIC WATER LEVEL 39 ft. below land surface measured on mo/day/yr 06/11/98
 Pump test data: Well water was 100 ft. after 4 hours pumping 1850 gpm
 Estimated Yield 1850 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 178 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 178 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 39 lbs/ft. Wall thickness or gauge No. .230
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 88 ft. to 168 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 178 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? WEST How many feet? 240

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	16	02 SILT 04 SANDY CLAY			
16	27	04 SANDY CLAY			
27	32	08 MEDIUM SAND 01 CLAY			
32	49	04 SANDY CLAY 08 MEDIUM SAND			
49	65	08 MEDIUM SAND 01 CLAY			
65	98	08 MEDIUM SAND			
98	114	08 MEDIUM SAND 01 CLAY			
114	123	08 MEDIUM SAND			
123	132	11 GRAVEL 01 CLAY			
132	143	11 GRAVEL 01 CLAY 31 CALICHE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/05/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/18/98 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWD-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 060 MEADE	SW 1/4 SW 1/4 SW 1/4	19	T 33 S	R 28 W

2 WATER WELL OWNER: QUICK, DAVID

RR#, St. Address, Box #: P.O. BOX 216

Board of Agriculture, Division of Water Resources

City, State, ZIP code : MEADE, KS 67864-

Application Number: 15,044

FROM	TO	LITHOLOGIC LOG
143	147	08 MEDIUM SAND
147	164	09 COARSE SAND 08 MEDIUM SAND 01 CLAY
164	168	05 SAND 15 CRS GRAVEL
168	180	04 SANDY CLAY
180	196	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 06/05/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/18/98 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Richmond*