

1 LOCATION OF WATER WELL: County: <u>Meade</u>		Fraction <u>NE 1/4 NE 1/4 SE 1/4</u>	Section Number <u>28</u>	Township Number <u>T 37 S</u>	Range Number <u>R 29 E</u>
Distance and direction from nearest town or city street address of well if located within city? <u>10 miles South and 7 miles West of Meade</u>					
2 WATER WELL OWNER: <u>Steve Frappier</u> RR#, St. Address, Box # : <u>Nxe Rte Box 4</u> City, State, ZIP Code : <u>Meade Kansas 67864</u>			Board of Agriculture, Division of Water Resources Application Number:		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>300</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. <u>200</u> ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL <u>8.1</u> ft. below land surface measured on mo/day/yr <u>8-8-86</u>			
		Pump test data: Well water was <u>8.1</u> ft. after <u>1 1/2</u> hours pumping <u>30</u> gpm			
		Est. Yield <u>50</u> gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter <u>8 1/8</u> in. to <u>300</u> ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		☒ Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) ☐ 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No <u>X</u>; If yes, mo/day/yr sample was submitted			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued <u>X</u> Clamped			
1 Steel 3 RMP (SR)		Welded			
☒ PVC 4 ABS		Threaded			
Blank casing diameter <u>5</u> in. to <u>300</u> ft., Dia		Casing height above land surface <u>241</u> in., weight lbs./ft. Wall thickness or gauge No. <u>200 lb</u>			
TYPE OF SCREEN OR PERFORATION MATERIAL:		☒ PVC 10 Asbestos-cement ☐ 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) ☐ 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)			
SCREEN OR PERFORATION OPENINGS ARE:		☒ Saw cut 11 None (open hole) ☐ 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 6 Wire wrapped 9 Drilled holes ☐ 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)			
SCREEN-PERFORATED INTERVALS:		From <u>260</u> ft. to <u>300</u> ft., From ft. to ft.			
GRAVEL PACK INTERVALS:		From <u>15</u> ft. to <u>300</u> ft., From ft. to ft.			
6 GROUT MATERIAL:		4 Other			
1 Neat cement ☒ Cement grout 3 Bentonite		Grout Intervals: From <u>Top</u> ft. to <u>15</u> ft., From ft. to ft.			
What is the nearest source of possible contamination:		☒ Livestock pens 14 Abandoned water well ☐ 1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well ☐ 2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below) ☐ 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage			
Direction from well?		How many feet? <u>5000</u>			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	10	Topsoil			
10	40	Sand & Gravel			
40	90	Brown Clay			
90	200	Blue Clay			
200	220	Gravel			
220	260	Blue Clay			
260	300	Gravel			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>8-8-86</u> and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. <u>101A</u> This Water Well Record was completed on (mo/day/yr) <u>8-21-86</u>					
under the business name of <u>Bartel Dry</u> by (signature) <u>Steve Bartel</u>					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					

OFFICE USE ONLY

T

R

EW

SEC.

1/4

1/4

1/4