

*The
Professionals*

MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269

P.O. Box A

GARDEN CITY, KANSAS 67846

Warren Fox
Meade County
10/8/97

Location: NW $\frac{1}{4}$ 19-33-29 - From Plains - 6 miles south to Caution Light,
3 miles east to Road 8, 1,900 ft. south & 100 ft. east

Static Water Level - 140'?

Test #1

0' to 3' - Top soil
3' to 8' - Brown clay 01
8' to 16' - Brown sandy clay 04
16' to 52' - Brown clay with white rock 01
52' to 67' - Brown sandy clay 04
67' to 81' - Fine to medium sand and gravel 17
81' to 99' - Brown clay 01
99' to 109' - Brown sandy clay with sand streaks 04
109' to 239' - Fine to medium sand and gravel 17
239' to 251' - Brown sandy clay 04
251' to 267' - Fine sand with blue clay streaks 07
267' to 323' - Fine to medium sand and gravel
323' to 377' - Fine to medium sand and gravel - 10% clay 17
377' to 395' - Blue clay 01
395' to 410' - Blue shale - hard 19

RECEIVED
OCT 11 1998
BUREAU OF WATER