


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Meade	Fraction NW 1/4 NW 1/4 NE 1/4	Section number 5	Township number 33	Range number 30
2. Distance and direction from nearest town or city: From SW edge of Plains, go 3 mi. south, 1/2 mi. west Street address of well location if in city:			3. Owner of well: Clair Hubert R.R. or street: R.R. City, state, zip code: Plains, Kansas, 67869.		
4. Locate with "X" in section below: 			Sketch map: Location of test hole NW corner of the NE 1/4, Sec. 5, T33S, R30W, Meade County, Kansas.		
5. Type and color of material			From	To	6. Bore hole dia. 28 in. Completion date 6-14-78 Well depth 460 ft.
Top Soil			0	10	7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
Fine Sand, clay streaks			10	55	8. Use: Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other <input type="checkbox"/>
Tan clay, sand streaks			55	78	9. Casing: Material <input checked="" type="checkbox"/> Steel Height: Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <input type="checkbox"/> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 42 lbs./ft. Dia. 16 in. to 260 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 219
Fine to medium sand, clay streaks			78	110	10. Screen: Manufacturer's name Doerr and Foster Type Louvre & Mill Slot Slot/gauze 1/8 Length 200' Set between 260 ft. and 460 ft. ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material 3.5 mm
Tan Clay			110	130	11. Static water level: 194 mo./day/yr. ft. below land surface Date 5-17-78
Fine to Medium sand			130	152	12. Pumping level below land surfaces: 266 ft. after 1 hrs. pumping 1683 g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 1800 g.p.m.
Tan clay, sand streaks			152	172	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>
Fine to medium sand, clay streaks			172	188	14. Well head completion: Pitless adapter 12 inches above grade
Tan and blue clay, sand streaks			188	210	15. Well grouted? <input type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 20 ft.
Blue clay			210	273	16. Nearest source of possible contamination: ft. UNK. Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
Fine to medium sand, blue clay streaks			273	304	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Layne, Bowler Model number 12TH HP 170 BHP Volts <input type="checkbox"/> Length of drop pipe 320 ft. capacity 1800 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
Blue clay, sand streaks			330	350	
Fine to medium sand, clay streaks, loose			350	460	
Blue clay, sand streaks			460	480	
18. Elevation:			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne-Western Co., Inc. 102 Business name Box 686, Garden City, KS. Address R. L. Vincent Signed R. L. Vincent Date 19 Jul 78 Authorized representative		
19. Remarks: Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5