


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Meade</b>	Fraction <b>SE 1/4 SE 1/4 NE 1/4</b>	Section number <b>22</b>	Township number <b>T 33 S</b>	Range number <b>R 30 E</b>
2. Distance and direction from nearest town or city: <b>6 miles S of Plains 1E, 1/2S, 600'W</b> Street address of well location if in city:				3. Owner of well: <b>Don Powell</b> R.R. or street: <b>R.R.</b> City, state, zip code: <b>Plains, Kansas</b>		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <b>28</b> in. Completion date <b>5-14-76</b> Well depth <b>422</b> ft.		
		<b>600' W of the SE corner of the NE 1/4, Sec. 22, T33S, R30W, Meade County, Kansas.</b>		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
5. Type and color of material				From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
Top soil				0	4	9. Casing: Material <b>STL</b> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>37</b> lbs./ft. Dia. <b>16</b> in. to <b>201</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>219</b>
Tan clay, caliche streaks				4	76	10. Screen: Manufacturer's name <b>Doerr &amp; Foster</b> Type <b>Louver &amp; Millislot</b> Dia. <b>16"</b> Slot/gauze <b>1/8"</b> Length <b>221'</b> Set between <b>201</b> ft. and <b>422</b> ft. ft. and <input type="checkbox"/> ft.
Fine to coarse sand, med. gravel, clay streaks				76	142	Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>1.8 to 5 mm</b>
Fine to coarse sand, clay streaks				142	238	11. Static water level: <input type="checkbox"/> mo./day/yr. <b>174</b> ft. below land surface Date <b>4-3-76</b>
Fine to coarse sand, medium gravel, blue clay streaks				238	282	12. Pumping level below land surfaces: <b>202</b> ft. after <b>1</b> hrs. pumping <b>1319</b> g.p.m. <b>220</b> ft. after <b>1</b> hrs. pumping <b>1977</b> g.p.m. Estimated maximum yield <b>2,000</b> g.p.m.
Blue sandy clay				282	296	13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>
Fine to coarse sand, medium gravel, clay streaks				296	378	14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade
Tan clay, sand streaks				378	404	15. Well grouted? <b>Yes</b> With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.
Fine to coarse sand, clay streaks				404	422	16. Nearest source of possible contamination: <b>Unk</b> ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
Tan sticky clay sand streaks				422	459	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <b>Layne &amp; Bowler</b> Model number <b>12KL</b> HP <b>125</b> Volts <input type="checkbox"/> Length of drop pipe <b>280</b> ft. capacity <input type="checkbox"/> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
Fine sand, clay streaks				459	512	
Tan clay, fine sand streaks				512	568	
Red bed				568	580	
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Layne-Western Co.</b> <b>150</b> Business name License No. Address <b>Garden City</b> Signed <b>[Signature]</b> Date <b>5-21-76</b> Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5