

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 060 MEADE NC 19 T 33 S R 30 W

Distance and direction from nearest town or city street address of well if located within city?

APPX 1/2 MILE E, 2 S, 3 E, 1/2 S & 1/2 E OF KISMET

2 WATER WELL OWNER: ORMISTON, ROCK

RR#, St. Address, Box #: 303 MAIN

Board of Agriculture, Division of Water Resources

City, State, ZIP code : KISMET, KS 67859-9612

Application Number: 41,578

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 478 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 203 ft. below land surface measured on mo/day/yr 12/08/97

Pump testdata: Well water was 420 ft. after 4 hours pumping 512 gpm

Estimated Yield 512 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 478 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;

If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL

CASING JOINTS: WELDED

Blank casing diameter 16 in. to 478 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 16 in., weight 42 lbs/ft. Wall thickness or gauge No. .250

TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 365 ft. to 475 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 478 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: NONE OBSERVED

Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	10	02 SILT			
10	40	01 CLAY			
40	60	05 SAND 11 GRAVEL 01 CLAY			
60	70	04 SANDY CLAY			
70	80	09 COARSE SAND 01 CLAY			
80	90	01 CLAY			
90	100	05 SAND 11 GRAVEL			
100	105	01 CLAY			
105	120	09 COARSE SAND 13 FINE GRAVEL			
120	140	08 MEDIUM SAND 09 COARSE SAND 04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/03/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/08/98 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
COUNTY: 060 MEADE : NC 1/4 1/4 1/4 : 19 : T 33 S : R 30 W

2 WATER WELL OWNER: ORMISTON, ROCK

RR#, St. Address, Box #: 303 MAIN

Board of Agriculture, Division of Water Resources

City, State, ZIP code : KISMET, KS 67859-9612

Application Number: 41,578

FROM	TO	LITHOLOGIC LOG
140	160	04 SANDY CLAY
160	172	08 MEDIUM SAND 04 SANDY CLAY
172	180	04 SANDY CLAY
180	200	07 FINE SAND 08 MEDIUM SAND 01 CLAY
200	220	01 CLAY 08 MEDIUM SAND 09 COARSE SAND
220	240	08 MEDIUM SAND 01 CLAY
240	260	01 CLAY
260	280	01 CLAY 05 SAND
280	290	08 MEDIUM SAND 01 CLAY
290	360	01 CLAY
360	380	08 MEDIUM SAND 09 COARSE SAND 10 V CRS SAND
380	400	05 SAND 01 CLAY
400	420	05 SAND 13 FINE GRAVEL
420	423	01 CLAY
423	440	08 MEDIUM SAND 09 COARSE SAND 13 FINE GRAVEL
440	450	08 MEDIUM SAND 09 COARSE SAND 04 SANDY CLAY
450	460	08 MEDIUM SAND 09 COARSE SAND 13 FINE GRAVEL
460	475	08 MEDIUM SAND 09 COARSE SAND 04 SANDY CLAY
475	480	04 SANDY CLAY
480	500	01 CLAY 31 CALICHE

3 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/03/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/08/98 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce Reichmuth