

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 060 MEADE SW 1/4 SW 1/4 SW 1/4 19 T 33 S R 30 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPX. 1/2 MILE EAST, 3 MILES SOUTH, 3 MILES EAST OF KISMET

2 WATER WELL OWNER: NEUMANN-WHEATLY FARMS INC  
 RR#, St. Address, Box #: 60382 SE BOTH AVE Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: ISABEL, KS 67065- Application Number: 41,580

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 543 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 204 ft. below land surface measured on mo/day/yr 12/01/97  
 Pump test data: Well water was 259 ft. after 4 hours pumping 1550 gpm  
 Estimated Yield 1550 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 24 in. to 543 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 02 IRRIGATION  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 543 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 282 ft. to 342 ft., From 460 ft. to 540 ft.  
 From 370 ft. to 440 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 543 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	10	02 SILT 04 SANDY CLAY			
10	35	04 SANDY CLAY			
35	48	05 SAND 11 GRAVEL			
48	55	04 SANDY CLAY			
55	75	05 SAND 11 GRAVEL			
75	80	01 CLAY			
80	92	05 SAND 11 GRAVEL			
92	100	04 SANDY CLAY 09 COARSE SAND			
100	140	01 CLAY 09 COARSE SAND			
140	160	04 SANDY CLAY 09 COARSE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/25/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 12/11/97 under the business name of HENKLE DRILLING & SUPPLY by (signature)

