

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Meade	C 1/4 NE 1/4 SE 1/4	31	T 33 S	R 30 EW

Distance and direction from nearest town or city street address of well if located within city?

8 2/3 mi S Plains, KS--

2 WATER WELL OWNER: Charter Prod.	#1 Fox Delbert A'
RR#, St. Address, Box #: 224 E. Douglas, Suite 400	Board of Agriculture, Division of Water Resources
City, State, ZIP Code: Wichita, KS 67202	Application Number: 920282

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 320 ft. ELEVATION:
	Depth(s) Groundwater Encountered 1. 160 ft. 2. 160 ft. 3. 160 ft. WELL'S STATIC WATER LEVEL 160 ft. below land surface measured on mo/day/yr 8/06/92 Pump test data: Well water was 190 ft. after 1 hours pumping 100 gpm Est. Yield 100 gpm: Well water was 190 ft. after 1 hours pumping 100 gpm Bore Hole Diameter 9 1/2 in. to 320 ft., and in. to 320 ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes ☒ No

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued ☒ Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 PVC	4 ABS	7 Fiberglass	Welded
Blank casing diameter 5 in. to 320 ft., Dia			Threaded
Casing height above land surface 24 in., weight			lbs./ft. Wall thickness or gauge No. 0.032
TYPE OF SCREEN OR PERFORATION MATERIAL:	5 Fiberglass	8 RMP (SR)	10 Asbestos-cement
1 Steel	3 Stainless steel	6 Concrete tile	9 ABS
2 Brass	4 Galvanized steel	5 Gauzed wrapped	8 Saw cut
SCREEN OR PERFORATION OPENINGS ARE:	1 Continuous slot	3 Mill slot	6 Wire wrapped
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify)
SCREEN-PERFORATED INTERVALS:	From 240 ft. to 320 ft.	From 240 ft. to 320 ft.	From 240 ft. to 320 ft.
GRAVEL PACK INTERVALS:	From 120 ft. to 320 ft.	From 120 ft. to 320 ft.	From 120 ft. to 320 ft.

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other	Hole Plug
GROUT INTERVALS:	From 1 ft. to 20 ft.	From 1 ft. to 20 ft.	From 1 ft. to 20 ft.	From 1 ft. to 20 ft.	From 1 ft. to 20 ft.
What is the nearest source of possible contamination:	1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
	2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
	3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
Direction from well?	East				

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	11	Sandy Clay	274	279	Clay
11	27	Clay	279	288	Sand
27	44	Sand	288	293	Clay
44	58	Clay	293	315	Sand
58	70	Sand	315	320	Blue Clay
70	77	Clay			
77	102	Sand			
102	111	Clay			
111	199	Sand			
199	210	Clay			
210	235	Sand			
235	238	Clay			
238	254	Sand			
254	261	Clay			
261	274	Sand			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 8/06/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. KWWCL-430. This Water Well Record was completed on (mo/day/yr) 8/06/92 under the business name of Howard Drlg. Co. Box 806 Beaver, OK 73932 by (signature) Howard Drlg. Co.

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.

#14740