

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 088 SEWARD NW 1/4 NE 1/4 SE 1/4 12 T 33 S R 31 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 3 MILES EAST AND 1/2 SOUTH OF KISMET

2 WATER WELL OWNER: DEKALB SWINE BREEDERS INC
 RR#, St. Address, Box #: P.O. BOX 429 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: PLAINS, KS 67869- Application Number: 21,974

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 485 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 220 ft. below land surface measured on mo/day/yr 05/31/95
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 200 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 17 1/2 in. to 485 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 03 FEEDLOT
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 8 in. to 485 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 7 lbs/ft. Wall thickness or gauge No. 410
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 365 ft. to 485 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 485 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTHEAST How many feet? 79

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	85	04 SANDY CLAY 31 CALICHE			
85	101	01 CLAY 31 CALICHE			
101	111	04 SANDY CLAY 05 SAND			
111	209	05 SAND 01 CLAY			
209	263	01 CLAY 05 SAND			
263	279	05 SAND 04 SANDY CLAY 15 CRS GRAVEL			
279	335	05 SAND 13 FINE GRAVEL			
335	354	07 FINE SAND 08 MEDIUM SAND			
354	398	05 SAND 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/31/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/02/95 under the business name of HENKLE DRILLING & SUPPLY by (signature)

