

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 088 SEWARD SE 1/4 NE 1/4 NE 1/4 22 T 33 S R 31 E

Distance and direction from nearest town or city street address of well if located within city?
 APPX. 1/2 MILE EAST, 2 SOUTH, 1 EAST & 800' SOUTH OF KISMET

2 WATER WELL OWNER: RINEHART, VEE Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: BOX 333
 City, State, ZIP code: KISMET, KS 67859-0333 Application Number: 43,124

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 561 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 212 ft. below land surface measured on mo/day/yr 03/27/98
 Pump testdata: Well water was 37 ft. after 4 hours pumping 1410 gpm
 Estimated Yield 1410 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 561 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 561 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 270 ft. to 330 ft., From 512 ft. to 522 ft.
 From 370 ft. to 500 ft., From 538 ft. to 558 ft.
 GRAVEL PACK INTERVALS: From 30 ft. to 561 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 30 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	19	02 SILT			
19	35	01 CLAY 36 GYP ROCK			
35	90	01 CLAY 31 CALICHE			
90	210	05 SAND 11 GRAVEL 01 CLAY			
90	210	20 LIMESTONE			
210	220	01 CLAY 05 SAND			
220	232	01 CLAY 20 LIMESTONE			
232	247	05 SAND 01 CLAY			
247	262	01 CLAY 05 SAND 20 LIMESTONE			
262	293	05 SAND 01 CLAY 20 LIMESTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/25/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/09/98 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 088 SEWARD	SE 1/4 NE 1/4 NE 1/4	22	T 33 S	R 31 E

2 WATER WELL OWNER: RINEHART, VEE
 RR#, St. Address, Box #: BOX 333 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: KISMET, KS 67859-0333 Application Number: 43,124

FROM	TO	LITHOLOGIC LOG
293	297	01 CLAY
297	317	05 SAND 01 CLAY
317	330	05 SAND
330	335	01 CLAY 05 SAND 28 ROCK
335	372	01 CLAY 05 SAND
372	399	05 SAND 14 MED GRAVEL
399	404	01 CLAY
404	500	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
500	510	04 SANDY CLAY 01 CLAY
510	524	FN-ME-CRS SAND 11 GRAVEL 01 CLAY
524	540	01 CLAY 05 SAND
540	558	05 SAND 01 CLAY
558	570	01 CLAY 04 SANDY CLAY
570	580	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/25/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/09/98 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichmuth*