

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 088 SEWARD NC 5/2 5/2 SE 1/4 23 T 33 S R 31 W

Distance and direction from nearest town or city street address of well if located within city?
 APPX 1/2 MILE E, 3 S, 1 1/2 E & 400' NORTH OF KISMET

2 WATER WELL OWNER: NEUMANN-WHEATLY FARMS INC
 RR#, St. Address, Box #: 60382 SE 80TH AVE Board of Agriculture, Division of Water Resources
 City, State, ZIP code: ISABEL, KS 67065- Application Number: 41,581

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 503 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 215 ft. below land surface measured on mo/day/yr 12/11/97
 Pump testdata: Well water was 265 ft. after 4 hours pumping 1615 gpm
 Estimated Yield 1615 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 503 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 503 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 260 ft. to 280 ft., From 0 ft. to 0 ft.
 From 320 ft. to 500 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 503 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	5	02 SILT			
5	50	01 CLAY			
50	70	05 SAND 11 GRAVEL			
70	80	01 CLAY			
80	100	05 SAND 11 GRAVEL			
100	140	05 SAND 11 GRAVEL 01 CLAY			
140	160	08 MEDIUM SAND 09 COARSE SAND			
160	180	08 MEDIUM SAND 09 COARSE SAND 01 CLAY			
180	200	05 SAND 13 FINE GRAVEL 01 CLAY			
200	220	08 MEDIUM SAND 09 COARSE SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/05/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/06/98 under the business name of HENKLE DRILLING & SUPPLY by (signature)

