

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 088 SEWARD NE 1/4 NW 1/4 NE 1/4 11 T 33 S R 31 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 2 MILES EAST OF KISMET

2 WATER WELL OWNER: DARRELL HEADRICK
 RR#, St. Address, Box #: BOX 22 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: KISMET, KS 67859- Application Number: 40976

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 488 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 223 ft. below land surface measured on mo/day/yr 12/23/94
 Pump test data: Well water was 288 ft. after 2 hours pumping 1500 gpm
 Estimated Yield 1500 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 488 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 488 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 275 ft. to 315 ft., From 380 ft. to 480 ft.
 From 337 ft. to 367 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 488 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	55	01 CLAY 04 SANDY CLAY			
55	69	01 CLAY			
69	82	04 SANDY CLAY 01 CLAY			
82	170	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL			
170	187	01 CLAY 04 SANDY CLAY			
187	210	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL			
210	216	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
216	221	01 CLAY 05 SAND			
221	275	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/22/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 12/30/94 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 088 SEWARD	NE 1/4 NW 1/4 NE 1/4	11	T 33 S	R 31 W

2 WATER WELL OWNER:	DARRELL HEADRICK	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	BOX 22	Application Number: 40976
City, State, ZIP code :	KISMET, KS 67859-	

FROM	TO	LITHOLOGIC LOG
275	313	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
313	336	01 CLAY
336	343	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
343	368	07 FINE SAND 09 COARSE SAND 01 CLAY
368	378	04 SANDY CLAY
378	441	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
441	485	06 VERY FN SAND 07 FINE SAND 04 SANDY CLAY
485	500	19 SHALE 04 SANDY CLAY 01 CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/22/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 12/30/94 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce J. Reichmuth