

Elite Irrigation & Drilling Inc

Po box 1818 Liberal, KS 67905

Test Hole Drilling Log

Customer: Mills Farms - Doug Mills

Date: 02/21/2019

Phone: -

1902 Road C

E-Logg: no Test #: 1

Hugoton, KS 67951

Driller: Mauricio

County: Seward

Quarter: NW SW NW Section:31 Township: 33s Range: 34w

GPS Location: 37.1381° -101.0673°

Total Pay: 309'

Total Depth: 600'

Description of Strata from the surface down.

(example: 3-50, 47. Sand; Footage is from 3-50 feet, pay = 47. Sand is the strata description.)

0-14. Top soil

14-52. Tan clay

52-70. Coarse sand

70-129. Clay

129-135. Rock/gravel (tight)

135-203. Clay

203-229. Coarse sand small clay strips

229-282, 22. Coarse sand

282-307, 19. Medium sand clay strips

307-396, 89. Coarse sand small gravel

396-40, 11. Medium sand

407-505, 98. Coarse sand

505-575, 70. Medium sand

575-600. Red bed