



# WINTER WILSON DRILLING CO.

INCORPORATED

Irrigation  
and Domestic  
Water Systems  
Complete Installation  
and Repairing

Phone 276-8269 • P.O. Box 493 • GARDEN CITY, KANSAS 67846

Bill Dale

1-13-75

Stevens County

Location: South of Moscow to highway 270, 3 miles east,  $2\frac{1}{2}$  south,  $\frac{1}{4}$  east, 100 ft. east of pivot

Test: #2

0	2	Top soil
2	8	Brown clay
8	69	Fine to med. sand & clay
69	80	Brown & gray clay
80	105	Brown clay
105	112	Fine to med. sand & gravel, 15% clay, loose
112	219	Brown clay
219	244	Fine to med. sand & gravel, 10% clay, loose
244	290	Brown sandy clay
290	305	Brown sandy clay, small streak of gravel 30%
305	346	Fine to med. sand & gravel, 10% clay, (loose)
346	357	Brown sandy clay
357	382	Fine to med. sand & gravel, 10% clay (loose)
382	395	Fine to med. sand & gravel, 15% clay (loose)

Phone 276-8269 • P.O. Box 493 • GARDEN CITY, KANSAS 67846

395	406	Fine to med. sand & gravel (loose)
406	410	Brown sandy clay & brown clay
410	425	Fine to med. sand & gravel, 20% clay (loose)
425	447	Fine to med. sand & gravel (loose)
447	455	Fine to med. sand & gravel, 30% clay (loose)
455	472	Fine to med. sand & gravel, 10% clay (loose)
472	495	Fine to med. sand & gravel, 15% clay (loose)
495	500	Brown clay
500	506	Fine to med. sand & gravel, 15% clay (loose)
506	515	Brown sandy clay
515	563	Fine to med. sand & gravel (loose)
563	575	Fine to med. sand & gravel, 15% clay (loose)
575	594	Fine to med. sand & gravel, 10% clay (loose)
594	600	Brown & gray clay, hard
600	605	Brown, gray & red clay (Hard)