

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 095 STEVENS NE 1/4 NE 1/4 NW 1/4 24 T 33 S R 36 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROXIMATELY 4 1/2 MILES WEST OF WOODS

2 WATER WELL OWNER: HEGER, ROBB Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: RT 1, BOX 81C
 City, State, ZIP code: HUGOTON, KS 67951- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 440 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 230 ft. below land surface measured on mo/day/yr 10/20/97
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 25 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 440 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: BLUED
 Blank casing diameter 5 in. to 440 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 340 ft. to 360 ft., From 420 ft. to 440 ft.
 From 380 ft. to 400 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 440 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	25	02 SILT 04 SANDY CLAY 07 FINE SAND			
25	35	01 CLAY			
35	50	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
50	130	01 CLAY			
130	160	04 SANDY CLAY			
160	195	07 FINE SAND 04 SANDY CLAY			
195	225	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
225	240	08 MEDIUM SAND 01 CLAY			
240	260	04 SANDY CLAY 07 FINE SAND			
260	275	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/20/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/29/97
 under the business name of DENNIS BOYD LTD & SUPPLY

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 095 STEVENS	NE 1/4 NE 1/4 NW 1/4	24	T 33 S	R 36 W

2 WATER WELL OWNER: HEBER, ROBB
 RR#, St. Address, Box #: RT 1, BOX 81C
 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : HUGOTON, KS 67951- Application Number:

FROM	TO	LITHOLOGIC LOG
275	292	07 FINE SAND
282	285	01 CLAY
285	340	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
340	365	07 FINE SAND 08 MEDIUM SAND 01 CLAY
365	380	04 SANDY CLAY
380	400	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
400	405	01 CLAY
405	406	20 LIMESTONE
406	420	01 CLAY 07 FINE SAND
420	430	01 CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/20/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/29/97 under the business name of HENKLE DRILLING & SUPPLY