

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 095 STEVENS	NW 1/4 NE 1/4 SE 1/4	02	T 33 S	R 36 W

Distance and direction from nearest town or city street address of well if located within city?

FROM HUGOTON; APPX 8 MILES WEST & 1 MILE NORTH

2 WATER WELL OWNER: THOMAS MILLER 1975 TRUST

RR#, St. Address, Box #: PO BOX 1330

Board of Agriculture, Division of Water Resources

City, State, ZIP code: WOODWARD, OK 73802-

Application Number: 31,744 & 31,128

3 LOCATE WELL'S LOCATION WITH

AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 522 ELEVATION: 0

Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \

WELL'S STATIC WATER LEVEL 270 ft. below land surface measured on mo/day/yr 08/31/07

Pump test data: Well water was 347 ft. after 4 hours pumping 1364 gpm

1

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

M

i

Bore Hole Diameter 36 in. to 522 ft., and in. to 0 ft.

l

WELL WATER TO BE USED AS: 02 IRRIGATION

e

W

Was a chemical/bacteriological sample submitted to department? No ;

\ /

If yes, mo/day/yr sample was submitted

Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL

CASING JOINTS: WELDED

Blank casing diameter 16 in. to 522 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250

TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:

From 302 ft. to 462 ft., From 0 ft. to 0 ft.

From 477 ft. to 517 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS:

From 20 ft. to 522 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL

Direction from well? NORTHEAST

How many feet? 120

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	9	04 SANDY CLAY 20 LIMESTONE			
9	59	04 SANDY CLAY			
59	132	05 SAND 14 MED GRAVEL 15 CRS GRAVEL			
132	151	04 SANDY CLAY			
151	184	04 SANDY CLAY			
184	220	05 SAND			
220	286	05 SAND 01 CLAY			
286	299	04 SANDY CLAY			
299	357	07 FINE SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/29/07 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 09/27/07

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 095 STEVENS	NW 1/4 NE 1/4 SE 1/4	02	T 33 S	R 36 W

2 WATER WELL OWNER: THOMAS MILLER 1975 TRUST

RR#, St. Address, Box # : PO BOX 1330

Board of Agriculture, Division of Water Resources

City, State, ZIP code : WOODWARD, OK 73802-

Application Number: 31,744 & 31,128

FROM	TO	LITHOLOGIC LOG
357	362	04 SANDY CLAY
362	375	07 FINE SAND 01 CLAY
375	399	05 SAND 13 FINE GRAVEL 28 ROCK
399	406	07 FINE SAND
406	420	05 SAND
420	462	05 SAND 01 CLAY
462	480	01 CLAY
480	517	07 FINE SAND
517	520	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/29/07 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 09/27/07

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

