

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 095 STEVENS SW 1/4 NW 1/4 NE 1/4 09 T 33 S R 37 W

Distance and direction from nearest town or city street address of well if located within city?

APPROX. 3/4 MILE NORTH & 1/4 EAST OF HUGOTON

2 WATER WELL OWNER: HANCOCK ELECTRIC
 RR#, St. Address, Box #: 1018 S. ADAMS Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HUGOTON, KS 67951- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 360 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 100 ft. below land surface measured on mo/day/yr 08/21/95
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 25 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 17/0 in. to 360 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 360 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. 265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 200 ft. to 280 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 340 ft. to 360 ft., From 0 ft. to 0 ft.
 From 25 ft. to 360 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	5	07 FINE SAND			
5	20	04 SANDY CLAY			
20	29	04 SANDY CLAY 07 FINE SAND			
29	69	07 FINE SAND 08 MEDIUM SAND			
69	78	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL			
78	85	05 SAND 11 GRAVEL			
85	99	04 SANDY CLAY 07 FINE SAND			
99	126	04 SANDY CLAY 31 CALICHE			
126	159	04 SANDY CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/25/95 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 09/01/95
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
COUNTY: 095 STEVENS : SW 1/4 NW 1/4 NE 1/4 : 09 : T 33 S : R 37 W

2 WATER WELL OWNER: HANCOCK ELECTRIC
RR#, St. Address, Box # : 1018 S. ADAMS Board of Agriculture, Division of Water Resources
City, State, ZIP code : HUGOTON, KS 67951- Application Number:

FROM	TO	LITHOLOGIC LOG
159	180	04 SANDY CLAY 07 FINE SAND 08 MEDIUM SAND
180	240	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
240	278	07 FINE SAND 08 MEDIUM SAND 01 CLAY
278	351	04 SANDY CLAY 07 FINE SAND
351	358	07 FINE SAND 08 MEDIUM SAND 01 CLAY
358	391	04 SANDY CLAY 07 FINE SAND
391	401	01 CLAY
401	516	04 SANDY CLAY 07 FINE SAND
516	522	04 SANDY CLAY 05 SAND
522	540	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/25/95 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 09/01/95
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Reichmann*