

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

|  |                                  |                      |                           |                        |
|--|----------------------------------|----------------------|---------------------------|------------------------|
| 1 LOCATION OF WATER WELL:<br>COUNTY: 095 STEVENS | Fraction<br>SW 1/4 SW 1/4 SW 1/4 | Section Number<br>26 | Township Number<br>T 33 S | Range Number<br>R 37 W |
|--|----------------------------------|----------------------|---------------------------|------------------------|

Distance and direction from nearest town or city street address of well if located within city?  
FROM HUGOTON; APPX 1 MILE EAST & 2 MILES SOUTH

2 WATER WELL OWNER: KARON K. CARPENTER  
RR#, St. Address, Box #: 37761 S. SKYLINE DR  
City, State, ZIP code: TUCSON, AZ 85739-1283  
Board of Agriculture, Division of Water Resources  
Application Number: 42076 & 15641

3 LOCATE WELL'S LOCATION WITH  
AN "X" IN SECTION BOX:

|     |     |    |     |    |
|-----|-----|----|-----|----|
| / \ |     |    |     |    |
| 1   | --- | NW | --- | NE |
| M   | W   |    |     | E  |
| i   |     |    |     |    |
| l   |     |    |     |    |
| e   |     |    |     |    |
|     |     | SW |     | SE |
| \ / |     |    |     |    |
|     | X   |    |     |    |

4 DEPTH OF COMPLETED WELL 573 ELEVATION: 0  
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 147 ft. below land surface measured on mo/day/yr 04/20/05  
Pump test data: Well water was 404 ft. after 4 hours pumping 732 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 573 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;  
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
Blank casing diameter 16 in. to 573 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

|                              |                          |                     |
|------------------------------|--------------------------|---------------------|
| SCREEN PERFORATED INTERVALS: | From 270 ft. to 300 ft., | From 0 ft. to 0 ft. |
|                              | From 338 ft. to 568 ft., | From 0 ft. to 0 ft. |
| GRAVEL PACK INTERVALS:       | From 20 ft. to 573 ft.,  | From 0 ft. to 0 ft. |
|                              | From 0 ft. to 0 ft.,     | From 0 ft. to 0 ft. |

6 GROUT MATERIAL 03 BENTONITE  
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
What is the nearest source of possible contamination: NONE OBSERVED  
Direction from well? How many feet? 0

| FROM | TO  | LITHOLOGIC LOG                      | FROM | TO | PLUGGING INTERVALS |
|------|-----|-------------------------------------|------|----|--------------------|
| 0    | 2   | 02 SILT                             |      |    |                    |
| 2    | 6   | 04 SANDY CLAY                       |      |    |                    |
| 2    | 6   | 04 SANDY CLAY                       |      |    |                    |
| 6    | 28  | 07 FINE SAND                        |      |    |                    |
| 28   | 36  | 01 CLAY                             |      |    |                    |
| 36   | 52  | 07 FINE SAND                        |      |    |                    |
| 52   | 90  | 05 SAND 11 GRAVEL                   |      |    |                    |
| 90   | 121 | 04 SANDY CLAY                       |      |    |                    |
| 121  | 150 | 07 FINE SAND 08 MEDIUM SAND 01 CLAY |      |    |                    |
| 150  | 207 | 04 SANDY CLAY 05 SAND               |      |    |                    |

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/13/05 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/16/05  
under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

|                           |                      |                |                 |              |
|---------------------------|----------------------|----------------|-----------------|--------------|
| 1 LOCATION OF WATER WELL: | Fraction             | Section Number | Township Number | Range Number |
| COUNTY: 095 STEVENS       | SW 1/4 SW 1/4 SW 1/4 | 26             | T 33 S          | R 37 W       |

2 WATER WELL OWNER: KARON K. CARPENTER  
RR#, St. Address, Box # : 37761 S. SKYLINE DR  
City, State, ZIP code : TUCSON, AZ 85739-1283

Board of Agriculture, Division of Water Resources  
Application Number: 42076 & 15641

| FROM | TO  | LITHOLOGIC LOG                      |
|------|-----|-------------------------------------|
| 207  | 219 | 05 SAND 01 CLAY                     |
| 219  | 221 | 04 SANDY CLAY                       |
| 221  | 252 | 07 FINE SAND 08 MEDIUM SAND 01 CLAY |
| 252  | 270 | 04 SANDY CLAY                       |
| 270  | 298 | 07 FINE SAND 08 MEDIUM SAND         |
| 298  | 338 | 04 SANDY CLAY                       |
| 338  | 365 | 07 FINE SAND                        |
| 365  | 370 | 04 SANDY CLAY                       |
| 370  | 396 | 05 SAND                             |
| 396  | 520 | 05 SAND                             |
| 520  | 524 | 01 CLAY                             |
| 524  | 568 | 05 SAND                             |
| 568  | 620 | 19 SHALE                            |

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/13/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/16/05 under the business name of HENKLE DRILLING & SUPPLY by (signature) 