

The Professionals

MINTER-WILSON DRILLING CO.
INCORPORATED

and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

City of Hugoton
Stevens County
9-26-87

Location: SW NE $\frac{1}{4}$ 16-33-37
 $\frac{1}{2}$ Block north of city office on
west side of road

Static Water Level - 116'

Test #1

0	5	Top soil
5	23	Brown clay
23	28	Brown sandy clay
28	76	Fine sand - tight
76	80	Fine to medium sand & gravel
80	98	Brown clay - brown rock - hard pull down
98	113	White clay - brown rock - hard
113	125	Brown clay - hard

125' Well
5" PVC
7-7/8" Hole
90' Plain
35' Perf.
1 Yd. Gravel

Marks: City of Hugoton Well #2