

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction NW 1/4 SW 1/4 SE 1/4 Section Number 17 Township Number T 33 S Range Number R 38 W
 COUNTY: STEVENS

Distance and direction from nearest town or city street address of well if located within city?
 FROM HUGOTON - 6 WEST ON HIGHWAY 56 - 1 N, 1/2 W & 1/4 NORTH

2 WATER WELL OWNER: PETTIJOHN, TOM
 RR#, St. Address, Box #: 206 S. LINCOLN
 City, State, ZIP code: HUGOTON, KS 67951- Board of Agriculture, Division of Water Resources
 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

\	/				
1		NW		NE	
M	W				E
i					
l		SW		SE	
e					
\	/				

4 DEPTH OF COMPLETED WELL 438 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 168 ft. below land surface measured on 11/22/96
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 70 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 438 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 438 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 333 ft. to 393 ft., From 0 ft. to 0 ft.
 From 413 ft. to 433 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 438 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE - NEW SITE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY FINE SAND			
20	40	FINE SAND CLAY IN LAYERS			
40	60	FINE - MED SAND GRAVEL			
60	80	CLAY CALACHIE FINE SAND			
80	160	CLAY			
160	200	CLAY FINE SAND IN LAYERS			
200	220	CLAY			
220	240	CLAY FINE SAND			
240	320	FINE SAND CLAY IN LAYERS			
320	340	FINE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (no/day/year) 12/16/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 12/17/96 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe Smith*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction NW 1/4 SW 1/4 SE 1/4 Section Number 17 Township Number T 33 S Range Number R 38 W
 COUNTY: STEVENS

2 WATER WELL OWNER: PETTIJOHN, TOM
 RR#, St. Address, Box #: 206 S. LINCOLN
 City, State, ZIP code: HUGOTON, KS 67951- Board of Agriculture, Division of Water Resources
 Application Number:

FROM	TO	LITHOLOGIC LOG
340	360	FINE - MED SAND
360	400	MED-COARSE SAND
400	420	CLAY
420	440	CLAY SANDSTONE
440	460	SANDSTONE
460	480	SANDSTONE REF REF