

1 LOCATION OF WATER WELL		Fraction	Section Number	Township Number	Range Number		
County: <u>Stearns</u>		<u>NE 1/4 NW 1/4 NE 1/4</u>	<u>14</u>	<u>T 33 S</u>	<u>R 38 E</u>		
Distance and direction from nearest town or city? <u>3 1/2 West Hugoton</u>			Street address of well if located within city? <u>AUG 27 3 80 22311 *****1.00</u>				
2 WATER WELL OWNER: <u>Stara Daris</u>							
RR#, St. Address, Box #: <u>R-R.</u>			Board of Agriculture, Division of Water Resources				
City, State, ZIP Code: <u>Hugoton Ks 67951</u>			Application Number:				
3 DEPTH OF COMPLETED WELL: <u>220</u> ft. Bore Hole Diameter: <u>10</u> in. to <u>220</u> ft., and <u>10</u> in. to <u>220</u> ft.							
Well Water to be used as:							
1 Domestic		3 Feedlot	6 Oil field water supply	9 Dewatering	12 Other (Specify below)		
2 Irrigation		4 Industrial	7 Lawn and garden only	10 Observation well			
Well's static water level: <u>130</u> ft. below land surface measured on <u>7</u> month <u>14</u> day <u>1980</u> year							
Pump Test Data: <u>8-9-90</u> Well water was <u>132</u> ft. after <u>2</u> hours pumping <u>15</u> gpm							
Est. Yield <u>8-9-90</u> gpm: Well water was <u>132</u> ft. after <u>2</u> hours pumping <u>15</u> gpm							
4 TYPE OF BLANK CASING USED:							
1 Steel		3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)	Casing Joints: <u>Glued</u> Clamped		
<u>2 PVC</u>		4 ABS	7 Fiberglass		Welded		
Blank casing dia <u>5</u> in. to <u>130</u> ft. Dia <u>5</u> in. to <u>130</u> ft. Dia <u>5</u> in. to <u>130</u> ft. Dia <u>5</u> in. to <u>130</u> ft.							
Casing height above land surface: <u>24</u> in., weight <u>258</u> lbs./ft. Wall thickness or gauge No. <u>258</u>							
TYPE OF SCREEN OR PERFORATION MATERIAL:							
1 Steel		3 Stainless steel	5 Fiberglass	8 RMP (SR)	11 Other (specify)		
2 Brass		4 Galvanized steel	6 Concrete tile	9 ABS	12 None used (open hole)		
Screen or Perforation Openings Are:							
1 Continuous slot		3 Mill slot	5 Gauzed wrapped	8 Saw cut	11 None (open hole)		
2 Louvered shutter		4 Key punched	6 Wire wrapped	9 Drilled holes			
			7 Torch cut	10 Other (specify)			
Screen-Perforation Dia <u>5</u> in. to <u>130</u> ft. Dia <u>5</u> in. to <u>130</u> ft. Dia <u>5</u> in. to <u>130</u> ft. Dia <u>5</u> in. to <u>130</u> ft.							
Screen-Perforated Intervals: From <u>130</u> ft. to <u>150</u> ft. From <u>160</u> ft. to <u>180</u> ft.							
From <u>190</u> ft. to <u>220</u> ft. From <u>190</u> ft. to <u>220</u> ft.							
Gravel Pack Intervals: From <u>13</u> ft. to <u>220</u> ft. From <u>13</u> ft. to <u>220</u> ft.							
5 GROUT MATERIAL:							
1 Neat cement		<u>2 Cement grout</u>	3 Bentonite	4 Other			
Grouted Intervals: From <u>4</u> ft. to <u>14</u> ft. From <u>4</u> ft. to <u>14</u> ft. From <u>4</u> ft. to <u>14</u> ft. From <u>4</u> ft. to <u>14</u> ft.							
What is the nearest source of possible contamination:							
<u>1 Septic tank</u>		4 Cess pool	7 Sewage lagoon	10 Fuel storage	14 Abandoned water well		
2 Sewer lines		5 Seepage pit	8 Feed yard	11 Fertilizer storage	15 Oil well/Gas well		
3 Lateral lines		6 Pit privy	9 Livestock pens	12 Insecticide storage	16 Other (specify below)		
Direction from well <u>South</u> How many feet <u>100</u> ? Water Well Disinfected? Yes <u>X</u> No							
Was a chemical/bacteriological sample submitted to Department? Yes <u>X</u> No <u>X</u> If yes, date sample							
was submitted <u>month</u> <u>day</u> <u>year</u> Pump Installed? <u>Yes</u> No							
If Yes: Pump Manufacturer's name <u>Flint & Walling</u> Model No. <u>15BA20</u> HP <u>1 1/2</u> Volts <u>230</u>							
Depth of Pump Intake <u>200</u> ft. Pumps Capacity rated at <u>13</u> gal./min.							
Type of pump: <u>1 Submersible</u> 2 Turbine 3 Jet 4 Centrifugal 5 Reciprocating 6 Other							
6 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was <u>(1)</u> constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was							
completed on <u>7</u> month <u>14</u> day <u>1980</u> year							
and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>127</u>							
This Water Well Record was completed on <u>8</u> month <u>25</u> day <u>1980</u> year under the business							
name of <u>Slalom Well Drilling</u> by (signature)							
7 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
		0	8	Silts cocoa colored			
		8	40	Sand fine brown			
		40	115	" w/ clays			
		115	125	Gravel coarse			
		125	132	Sand calcified			
		132	154	Gravel w/ clays			
		154	160	hard shell			
		160	180	Silts gray tan w/ rock			
		180	194	Stringers & sand			
		194	220	Silt walls w/ f. sand			
ELEVATION:		194	220	Sand coarse w/ sand			
Depth(s) Groundwater Encountered 1. <u>130</u> ft. 2. <u>130</u> ft. 3. <u>130</u> ft. 4. <u>130</u> ft. (Use a second sheet if needed)							
INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.							

OFFICE USE ONLY

T

33

R

38

FWD

SEC.

14

NE 1/4 NW 1/4 NE 1/4