


USE TYPEWRITER OR BALL
POINT PEN—PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment—Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Stevens</u>	Fraction <u>SE 1/4 SW 1/4 SW 1/4</u>	Section number <u>22</u>	Township number <u>T 33 S R 39 E/W</u>	Range number <u>39</u>
2. Distance and direction from nearest town or city: Street address of well location if in city:				3. Owner of well: R.R. or street: City, state, zip code:		
<u>11 W-15</u> <u>HUGOTON, K_n</u>				<u>W.E. Demuth</u> <u>519 S. Jackson</u> <u>HUGOTON K_n 67951</u>		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>10</u> in. Completion date <u>9-27-77</u> Well depth <u>160</u> ft.		
				7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☒ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material ☐ Height: Above or below Threaded ☐ Welded ☐ Surface <u>12</u> in. RMP ☐ PVC ☒ Weight ☐ lbs./ft. Dia. <u>5</u> in. to <u>160</u> ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. <u>250</u>		
5. Type and color of material				From	To	10. Screen: Manufacturer's name <u>Slocum</u>
<u>Sandy light gray</u>				<u>0</u>	<u>3</u>	Type <u>Saw cut</u> Dia. <u>5"</u>
<u>Sand tan silty</u>				<u>3</u>	<u>11</u>	Slot/gauze <u>1/8</u> Length <u>40'</u>
<u>11 redish w/rip</u>				<u>11</u>	<u>22</u>	Set between <u>100</u> ft. and <u>120</u> ft. <u>140</u> ft. and <u>160</u> ft.
<u>Clays orange Red w/white caliche</u>				<u>22</u>	<u>32</u>	Gravel pack? ☒ Size range of material <u>1/8 - 1/4</u>
<u>Sand redish</u>				<u>32</u>	<u>44</u>	11. Static water level: <u>80</u> ft. below land surface Date <u>9-27-77</u>
<u>11 Brown coarse</u>				<u>44</u>	<u>80</u>	12. Pumping level below land surfaces: <u>80</u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>20</u> g.p.m.
<u>Clays w/sand & gravel</u>				<u>80</u>	<u>88</u>	13. Water sample submitted: <u> </u> mo./day/yr. ☐ Yes ☒ No Date <u> </u>
<u>Clays redish</u>				<u>88</u>	<u>94</u>	14. Well head completion: ☐ Pitless adapter <u>12</u> inches above grade
<u>Clay ball - red + tan w/gravel & caliche</u>				<u>94</u>	<u>108</u>	15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From <u>3</u> ft. to <u>13</u> ft.
<u>Sand - med. fine w/clay ball & gravel</u>				<u>108</u>	<u>120</u>	16. Nearest source of possible contamination: <u> </u> ? ft. <u> </u> Direction <u> </u> Type <u> </u>
<u>Clays light w/gravel</u>				<u>120</u>	<u>140</u>	Well disinfected upon completion? ☒ Yes ☐ No
<u>Clays w/sand layers</u>				<u>140</u>	<u>160</u>	17. Pump: ☐ Not installed Manufacturer's name <u> </u> Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m. Type: <u>windmill</u> ☐ Submersible ☐ Turbine ☐ Jet ☒ Reciprocating ☐ Centrifugal ☐ Other
<u>Clays mostly tan</u>				<u>160</u>	<u>260</u>	
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Slocum Drilling</u> <u>127</u> Business name <u>HUGOTON K_n</u> License No. <u> </u> Address <u>Paul Slocum</u> Date <u>10-14</u> Signed <u> </u> Authorized representative		
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						